

UNITED STATES DISTRICT COURT
DISTRICT OF NEVADA

Jed Margolin,

Plaintiff

v.

Charles F. Bolden, Administrator,
National Aeronautics and Space Administration,

Defendant.

Appendix

Jed Margolin
1981 Empire Rd.
VC Highlands, NV 89521-7430
Phone: 775-847-7845
Email: jm@jmargolin.com

Dated: July 31, 2009

Appendix - Index

I. Exhibit 1 - Margolin’s claim against NASA for infringing on his patent in the X-38 project, filed June 17, 2003 A2

II. Exhibit 2 - Margolin’s Freedom of Information Act Request, asking for information relating to Margolin’s claim, emailed June 28, 2008 A17

III. Exhibit 3 - NASA’s response, dated August 5, 2008, asking for a 90-day extension of time to respond to Margolin’s FOIA Request A19

IV. Exhibit 4 - Margolin’s letter, dated August 8, 2008, giving NASA the 90-day extension it had requested A21

V. Exhibit 5 - Margolin’s fax to Acting Administrator Scolese, dated April 6, 2009, detailing the bad faith NASA had shown him, that NASA had still not responded to his FOIA request, and asking him to confirm he had exhausted all the administrative remedies NASA had to offer A23

VI. Exhibit 6 - NASA’s email response, dated May 14, 2009, to Margolin’s FOIA Request A27

VII. Exhibit 7 - Letter from NASA to Robert Adams of Optima Technology Group denying Optima’s claim for patent infringement in the X-38 project A30

VIII. Exhibit 8 - Margolin’s FOIA Appeal, sent June 10, 2009 A36

IX. Exhibit 9 - USPS confirmation that Margolin’s FOAI Appeal was delivered to NASA June 12, 2009 A57

X. Exhibit 10 - Letter from Margolin to Randolph Harris (NASA), dated July 21, 2009 A59

XI. Exhibit 11 - Email from Jan McNutt (NASA) to Margolin, dated July 24, 2009 asking for a 20-day extension A61

XII. Exhibit 12 - Email from Margolin to Jan McNutt (NASA), dated July 24, 2009, The answer is “No.” A63

XIII. Exhibit 13 - *Synthetic Vision Technology for Unmanned Systems: Looking Back and Looking Forward* by Jeff Fox, Michael Abernathy, Mark Draper and Gloria Calhoun, AUVSI's **Unmanned Systems**, December 2008, pages 27-28. A66

XIV. Exhibit 14 - **Synthetic Vision Technology for Unmanned Aerial Systems: The Real Story** By Jed Margolin, January 7, 2009
www.jmargolin.com/svr/auvsi_response_index.htm A69

XV. Exhibit 15 - Email from Brett Davis, Editor of AUVSI Magazine to Margolin, dated January 30, 2009A127

Exhibit

1

Jed Margolin
Phone: (408) 238-4564

3570 Pleasant Echo Dr.
Email: jm@jmargolin.com

San Jose, CA 95148-1916
June 17, 2003

Mr. Alan J. Kennedy
Director, Infringement Division
Office of the Associate General Counsel
National Aeronautics and Space Administration
Headquarters
Washington, DC 20546-0001

Attn: GP(02-37016)

Dear Mr. Kennedy,

I have received your letter dated June 11, 2003.

In my contacts with NASA personnel I have repeatedly stressed my desire that this matter be resolved in a friendly manner. However, since NASA has rejected my request to consider a license proffer and in view of your letter of June 11, it is clear that NASA has decided to handle this in an adversarial manner.

Before I respond to your letter in detail, I want to make things easier for me by withdrawing my U.S. Patent **5,566,073 Pilot Aid Using a Synthetic Environment** from this administrative claim in order to focus more directly on NASA's infringement of my U.S. Patent **5,904,724 Method and Apparatus For Remotely Piloting an Aircraft**. However, I reserve the right to file a claim concerning the '073 patent at a later time.

(1) The identification of all claims of the patent(s) alleged to be infringed.

As I stated in my email of May 13, 2003 to Mr. Hammerle of LARC and in my fax of June 7, 2003 to you, I have no way of determining exactly which claims the X-38 project may have infringed unless NASA makes a full and complete disclosure to me of that project. I also have no way of determining if NASA has (or has had) other projects that also infringe on my patent unless NASA makes a full and complete disclosure of those projects as well.

Therefore, in order to answer your question, I must request that NASA make a full and complete disclosure to me of the X-38 project as well as any other current or past projects that may infringe on my patent.

If this information requires a security clearance (I have none) I suggest you start the required security investigation immediately. If there is further information that you require in this regard feel free to contact me.

- (2) *The identification of all procurements known to the claimant or patent owner which involve the alleged infringing item or process, including the identity of the vendor or contractor and the Government procuring activity.*

As I stated in my fax to you of June 7, 2003, I became aware that NASA was using synthetic vision in the X-38 project in the January 2003 issue of NASA Tech Briefs, page 40, **"Virtual Cockpit Window" for a Windowless Aerospacecraft**. The article is available at: <http://www.nasatech.com/Briefs/Jan03/MSC23096.html>

This led me to Rapid Imaging Software, Inc. and their press release (<http://www.landform.com/pages/PressReleases.htm>) which states:

"On December 13th, 2001, Astronaut Ken Ham successfully flew the X-38 from a remote cockpit using LandForm VisualFlight as his primary situation awareness display in a flight test at Edwards Air Force Base, California. This simulates conditions of a real flight for the windowless spacecraft, which will eventually become NASA's Crew Return Vehicle for the ISS. We believe that this is the first test of a hybrid synthetic vision system which combines nose camera video with a LandForm synthetic vision display. Described by astronauts as 'the best seat in the house', the system will ultimately make space travel safer by providing situation awareness during the landing phase of flight."

The RIS press release provided a link to an article in *Aviation Week & Space Technology*: http://www.aviationnow.com/avnow/news/channel_space.jsp?view=story&id=news/sx381211.xml

As a result of more searching I discovered a link to a Johnson Space Center SBIR Phase II award to Rapid Imaging Systems at <http://sbir.gsfc.nasa.gov/SBIR/successes/ss/9-058text.html> .

It includes a particularly relevant paragraph:

The Advanced Flight Visualization Toolkit (VisualFlight™) project is developing a suite of virtual reality immersive telepresence software tools which combine the real-time flight simulation abilities with the data density of a Geographic Information System (GIS). This technology is used for virtual reality training of crews, analysis of flight test data, and as an on-board immersive situation display. It will also find application as a virtual cockpit, and in teleoperation of remotely piloted vehicles.

The emphasis on *virtual reality immersive telepresence* and *teleoperation of remotely piloted vehicles* is mine.

A search of the SBIR archive shows the following entries.

For 2001 Phase I:

Rapid Imaging Software, Inc.
1318 Ridgcrest Place S.E.
Albuquerque, NM 87108-5136
Mike Abernathy (505) 265-7020
01 H6.02-8715 JSC
Integrated Video for Synthetic Vision Systems

For 2001 Phase II:

Rapid Imaging Software, Inc.
 1318 Ridgecrest Place S.E.
 Albuquerque , NM 87108-5136
 Carolyn Galceran (505) 265 - 7020
 01-2-H6.02-8715 JSC

Since my sources of information are limited to those available to the public (magazines such as *Aviation Week & Space Technology* as well as whatever I can find on the Internet) I have no way of knowing if there are other procurements, vendors, contractors, and Government procuring activity related to Claim I-222.

I believe that NASA is in a better position to know what it is (or has been) working on than I am.

- (3) *A detailed identification of the accused articles or processes, particularly where the article or process relates to a component or subcomponent of the item procured, an element by element comparison of the representative claims with the accused article or process. If available, this identification should include documentation and drawings to illustrate the accused article or process in suitable detail to enable verification of the infringement comparison.*

I believe I have answered this in section (2) as much as I am able to without NASA's cooperation.

- (4) *The names and addresses of all past and present licenses under the patent(s), and copies of all license agreements and releases involving the patent.*

There are no past licenses for this patent, and as of this date there are no present licenses for this patent. Naturally, I reserve the right to license this patent in the future as I see fit.

- (5) *A brief description of all litigation in which the patent(s) has been or is now involved, and the present status thereof.*

There has been no past litigation involving this patent, and as of this date there is no present litigation regarding this patent.

- (6) *A list of all persons to whom notices of infringement have been sent, including all departments and agencies of the Government, and a statement of the ultimate disposition of each.*

As of this date NASA is the only agency or department of the Government against which I have filed a claim.

5/11/03 – sent email to comments@hq.nasa.gov

*I believe that NASA may have infringed on one or more of my U.S. Patents.
How do I file a claim and whom do I contact?*

5/11/03 – Received reply:

*Date: Sun, 11 May 2003 17:48:46 -0400 (EDT)
From: "PAO Comments" <comments@bolg.public.hq.nasa.gov>
Message-ID: <200305112148.h4BLmkhJ011314@bolg.public.hq.nasa.gov>
To: <jm@jmargolin.com>
Subject: Thank you for your email.*

Thank you for your message to the NASA Home Page. The Internet Service Group will attempt to answer all e-mail regarding the site, but cannot guarantee a response by a particular time. The group will not be able to answer general inquiries regarding NASA, which should instead be sent to public-inquiries@hq.nasa.gov

5/11/03 – Sent email to <public-inquiries@hq.nasa.gov>

*I believe that NASA may have infringed on one or more of my U.S. Patents.
How do I file a claim and whom do I contact?*

Jed Margolin

As far as I can tell I did not receive a response.

5/12/03 – Sent email to j.c.midgett@larc.nasa.gov (found on Web site)

*I believe that NASA may have infringed on one or more of my U.S. Patents
How do I file a claim and whom do I contact?
(Or is my only recourse to sue in Federal Court?)*

Jed Margolin

5/12/03 – Received reply:

Mr. Margolin,

Thank you for contacting NASA with your concerns. I have referred this matter to the Patent Counsel Office, and they will be contacting you to work with you on this issue.

*Best wishes,
Jesse Midgett*

5/12/03 – Given my experience with trying to contact Government officials via email (or mail, or fax) I hadn't waited for the reply from J. Midgett. I had found the web site for the LARC (NASA Langley) Patent Counsel Office, and called up. I was connected to Kurt Hammerle and we had a nice talk. I sent him an email the next day (May 13, 2003).

I received a phone call from Barry Gibbens (757-864-7141) who, apparently, was calling because of my email to J.C.Midgett and hadn't seen the email I sent to K. Hammerle. (I explained to him what I had done.) We had a nice talk. He said he had already sent me a letter.

I received his letter and sent a reply on May 18, 2003 (USPS), adding to the email I had sent K. Hammerle.

Thursday, June 5, 2003 – Received message from B. Gibbens, asking me to call him because I should contact Alan Kennedy at NASA Headquarters (202-358-2065).

Friday, June 6, 2003 - I called B. Gibbens. Then I called A. Kennedy but he was out.

Saturday, June 7, 2003 – Sent a fax to A. Kennedy. The first number I tried (202-358-4341) only accepted 4 pages (out of 13). I tried a few times. Then I tried 202-358-2741. It turned out that 4341 was the correct number and that 2741 was another group. As a result, A. Kennedy initially only got 4 pages.

Monday, June 9, 2003 – Received message from A. Kennedy and called him back.

He had not gotten the fax so he went and found it. I learned the next day that he had only gotten 4 pages.

We had a “free and frank” discussion. I stressed that I wanted to resolve it in a friendly manner and that I preferred to have NASA buy the patent for the Government.

Tuesday, June 10, 2003 – Received a message from A. Kennedy and called him back.

He said that his Manager has turned down my request that NASA consider a license proffer and has decided to handle it as a Claim, and that the investigation would take 3-6 months.

However, NASA is not the only agency or department of the Government I have contacted.

7/5/1999 Email to: lbirckelbaw@darpa.mil

Dr. Birckelbaw, Project Manager for the UCAV contract awarded to Boeing.

Introduced myself and asked if DARPA was interested in my patent.

Response: none

7/26/1999 USPS Mail to:

Dr. Larry Birckelbaw
Program Manager, Aerospace Systems
DARPA Tactical Technology Office
3701 North Fairfax Drive
Arlington, VA 22203-1714

Introduced myself and asked if DARPA was interested in my patent. Enclosed copy of patent.

Response: none

Office of the Secretary of Defense (OSD)

Mr. E.C. "Pete" Aldridge
Under Secretary of Defense for Acquisition, Technology, and Logistics
U.S. Department of Defense

Contact Method: Email: webmaster@acq.osd.mil

May 3, 2002 and June 6, 2002

Response: none

Army - AATD, Fort Eustice, VA.

Col. Wado Carmona, Commander
Applied Aviation and Training Directorate (AATD)
Army Aviation and Missile Command
Ft. Eustice, VA

Contact Method:

Email: Ms. Lauren L. Sebring lsebring@aatd.eustis.army.mil
757-878-4828, fax: 757-878-0008

June 1, 2002

Phone Call Followup: She suggested I talk to Mr. Jack Tansey

Mr. Jack Tansey, Business Development 757-878-4105

June 18, 2002

Email Followup: jtansey@aatd.Eustis.army.mil

June 18, 2002

Air Force Research Laboratory (AFRL)

Dr. Barbara Wilson

Contact Method: email (Barbara.Wilson@wpafb.af.mil)

July 17, 2002

Response - none

Air Force Research Laboratory (AFRL)
 Dr. R. Earl Good, Director,
 Directed Energy Directorate
 Air Force Research Laboratory
 Kirtland Air Force Base, NM 87117-5776
 Contact Method: Fax (505-846-0423)
 Response: none

July 23, 2002

 Department of the Air Force
 Dr. James G. Roche
 Secretary of the Air Force
 Washington, DC

Contact Method: Fax (703-695-8809)

July 28, 2002

Response: Letter from
 Lt. General Charles F. Wald
 Deputy Chief of Staff, Air & Space Operations, USAF

August 13, 2002

(7) *A description of Government employment or military service, if any, by the inventor and/or patent owner.*

I have never been employed by the U.S. Government (or any other government). Likewise, I have never been in military service (in the United States or elsewhere). In the interests of full disclosure, I worked for three summers (1967, 1968, 1969) at the RCA Astro-Electronics Division in Hightstown, NJ . (They had a summer job program for students.)

(8) *A list of all Government contracts under which the inventor, patent owner, or anyone in privity with him performed work relating to the patented subject matter.*

None. I did this entirely on my own dime.

(9) *Evidence of title to the patent(s) alleged to be infringed or other right to make the claim.*

This appears to be a two-part question. Does the patent belong to Jed Margolin, and am I that Jed Margolin?

Part 1 - If you look at the front page of the '724 patent you will see that it was, indeed, issued to Jed Margolin, 3570 Pleasant Echo Dr., San Jose, CA.

If you contact the U.S. Patent and Trademark Office, Document Services Department (703-308-9726), you can order an Abstract of Title to verify that I own the patent. According to 37 CFR 1.12, assignment records are also open to public inspection at the United States Patent and Trademark Office.

Part 2 - If you look up Jed Margolin, 3570 Pleasant Echo Dr., San Jose, CA, in a telephone directory you will find assigned to it the telephone number 408-238-4564.

When you called me on June 9 and June 10, that was the number you called.

Other than my affirming that I am, indeed, the Jed Margolin in question, I can only suggest that you contact my cousin Lenny (oops, I mean Dr. Len Margolin) who is employed by Los Alamos National Laboratory, and ask him if he has a cousin Jed who is an engineer and an inventor, and who possesses the Margolin gene for being very persistent. (Some say stubborn.) The last time I saw him was in Ann Arbor, Michigan, after he had just passed the orals for his doctorate. (He bought me a beer at a place on South University.)

(10) *A copy of the Patent Office file of the patent, if available, to claimant.*

I do not have a copy of the USPTO's patent file. What I have is my prosecution file which contains, among other things, privileged communications between my patent attorney and myself.

Besides, in our telephone conversation of June 10, you stated that one of the research centers (I believe it was LARC) had already ordered the file.

(11) Pertinent prior art known to claimant, not contained in the Patent Office file, particularly publications and foreign art.

I have found no relevant prior art.

However, there is an interesting article in the June 2, 2003 issue of *Aviation Week & Space Technology* on pages 48-51 entitled **GA Riding 'Highway-in-the-Sky'** which describes, among other things, the work of Dennis B. Berlinger, lead scientist for flight deck research at the FAA's Civil Aeromedical Institute (CAMI) regarding what is called **Performance-Controlled Systems**. In the Specification of my '724 patent I call it **First Order RPV Flight Control Mode**. In Claim 18:

18. The station of claim 13, wherein said set of remote flight controls are configured to allow inputting absolute pitch and roll angles instead of pitch and roll rates.

An Internet search turned up Mr. Berlinger's report **Applying Performance-Controlled Systems, Fuzzy Logic, and Fly-By-Wire Controls to General Aviation** as DOT/FAA/AM-02/7.

I am pleased that Mr. Berlinger's May 2002 study confirms the value of Performance-Controlled Systems in piloted aircraft and I believe that teaching it in my '724 patent (filed January 19, 1999) gave an additional novel and useful aspect to my invention.

(The article also describes the Synthetic Vision system used in the FAA's Capstone program.)

If you have any further questions, please contact me.

Sincerely yours,

Jed Margolin

Enclosed: Response from General Wald
AWST article
Berlinger Report
U.S. Patent 5,904,724



DEPARTMENT OF THE AIR FORCE
HEADQUARTERS UNITED STATES AIR FORCE
WASHINGTON, DC

13 Aug 02

HQ USAF/XO
1630 Air Force Pentagon
Washington, DC 20330-1630

Mr. Jed Margolin
3570 Pleasant Echo Dr.
San Jose, CA 95148-1916

Dear Mr. Margolin

On behalf of Secretary Roche, thank you for providing your ideas on ways to improve UAV control technology. As you know, we are now operating the Global Hawk and Predator systems in reconnaissance roles, and envision expanding unmanned aircraft applications into the weapons delivery mission area with theUCAV and the Predator/Predator B aircraft. Certainly we see a growing role for UAVs in the Air Force as technology advances and we gain experience in their operation. The improved control methods you have patented may well play a part in future UAV design. I suggest that you present these concepts to the various UAV manufacturers who are in the business of designing systems to meet our operational requirements. They can offer the best assessment on the overall feasibility of integrating your technology. I suggest a similar approach regarding your patented laser techniques.

Again, thank you for taking the time to offer these suggestions. I admire your ingenuity, and appreciate your desire to help us improve our national defense capabilities.

Sincerely

A handwritten signature in black ink, appearing to read "Charles F. Wald".

CHARLES F. WALD, Lt Gen, USAF
Deputy Chief of Staff
Air & Space Operations

cc:
SAF/AQ
AF/XOR



US005904724A

United States Patent [19]

[11] Patent Number: **5,904,724**

Margolin

[45] Date of Patent: **May 18, 1999**

[54] **METHOD AND APPARATUS FOR REMOTELY PILOTING AN AIRCRAFT**

5,406,286	4/1995	Tran et al.	342/13
5,446,666	8/1995	Bauer	364/434
5,552,983	9/1996	Thornberg et al.	364/424.027
5,581,250	12/1996	Khviliviky	340/961

[76] Inventor: **Jed Margolin**, 3570 Pleasant Echo, San Jose, Calif. 95148

OTHER PUBLICATIONS

[21] Appl. No.: **08/587,731**

Lyons, J.W., "Some Navigational Concepts for Remotely Piloted Vehicles", AGARD Conference Proceed. n 176, Med. Accur. Low Cost Navig. at Avion, Panel Tec. Meeting, 5-1-5-15, Sep. 1975.

[22] Filed: **Jan. 19, 1996**

"US GeoData Digital Line Graphs", U.S. Dept. of the Interior, U.S. Geol. Surv. Earth Sci. Info Ctr. (Factsheet) Jun. 1993.

[51] Int. Cl.⁶ **G06F 165/00; H04N 7/18**

"US GeoData Digital Elevation Models", U.S. Dept. of the Interior, U.S. Geol. Surv. Earth Sci. Info Ctr. (Factsheet) Jun. 1993.

[52] U.S. Cl. **701/120; 701/2; 701/24; 244/189; 244/190; 348/114**

[58] **Field of Search** 364/423.099, 424.012, 364/424.013, 424.021, 424.022, 449.2, 449.7, 460, 439, 424.028; 340/825.69, 825.72, 967, 989, 991, 992, 993; 244/189, 190, 181, 17.13, 3.11, 3.15; 348/42, 51, 113, 114, 117, 123, 143; 382/154; 395/118, 119, 125

Shifrin, Carole A., "Gripen Likely to Fly Again Soon," *Aviation Week & Space Technology*, Aug. 23, 1993, pp. 72-73.

[56] References Cited

Primary Examiner—Tan Q. Nguyen
Attorney, Agent, or Firm—Blakely, Sokoloff, Taylor and Zafman LLP


U.S. PATENT DOCUMENTS

3,742,495	6/1973	Diamantides	342/64
3,795,909	3/1974	Vehrs, Jr.	343/7
4,218,702	8/1980	Brocard et al.	348/144
4,405,943	9/1983	Kanaly	358/133
4,467,429	8/1984	Kendig	343/433
4,660,157	4/1987	Beckwith et al.	345/421
4,739,327	4/1988	Konig et al.	342/26
4,760,396	7/1988	Barney et al.	342/65
4,835,532	5/1989	Fant	382/284
4,855,822	8/1989	Naredra et al.	364/423.099
4,964,598	10/1990	Berejik et al.	244/190
5,015,187	5/1991	Lord	364/462
5,072,396	12/1991	Fitzpatrick et al.	364/450
5,086,396	2/1992	Waruszewski, Jr.	364/454
5,155,683	10/1992	Rahim	364/424.029
5,179,638	1/1993	Dawson et al.	395/125
5,240,207	8/1993	Eiband et al.	364/423.099
5,257,347	10/1993	Busbridge et al.	395/129
5,266,799	11/1993	Steinitz et al.	324/330
5,272,639	12/1993	McGuffin	364/449
5,335,181	8/1994	McGuffin	364/443
5,381,338	1/1995	Wysocki et al.	348/116

[57] ABSTRACT

A method and apparatus that allows a remote aircraft to be controlled by a remotely located pilot who is presented with a synthesized three-dimensional projected view representing the environment around the remote aircraft. According to one aspect of the invention, a remote aircraft transmits its three-dimensional position and orientation to a remote pilot station. The remote pilot station applies this information to a digital database containing a three dimensional description of the environment around the remote aircraft to present the remote pilot with a three dimensional projected view of this environment. The remote pilot reacts to this view and interacts with the pilot controls, whose signals are transmitted back to the remote aircraft. In addition, the system compensates for the communications delay between the remote aircraft and the remote pilot station by controlling the sensitivity of the pilot controls.

20 Claims, 7 Drawing Sheets



GA Riding 'Highway-in-the-Sky'

General aviation sector reaps the benefits of research originally conducted for military, commercial transport cockpits

BRUCE D. NORDWALL/WASHINGTON and OKLAHOMA CITY

General aviation aircraft are finally catching up with some of the advances found in the latest commercial transports and military cockpits, and in one particular sphere—display innovations—GA is actually taking the lead.

Researchers in industries and universities around the world have been pursuing a more intuitive guidance display for pilots for years. In general, this elusive presentation is referred to as highway-in-the-sky (HITS) (*AW&ST* Apr. 20, 1998, p. 58). In a twist that may foreshadow future advances, it was a general aviation aircraft that received the FAA's first certification of HITS technology for navigation guidance.

Instead of following course deviation

indicators and altimeters, a pilot using this HITS presentation flies through a series of 3D boxes on a multifunction display. By maneuvering through the 400 X 320-ft. boxes spaced at 2,000-ft.

Flying through "boxes in the sky" keeps pilots on course and altitude during a simulated curved instrument approach down the mountainous Gastineau Channel to Juneau, Alaska.

intervals along the planned GPS route of flight, the pilot keeps the aircraft on course and altitude, which is particularly helpful for a descending, curved instrument approach.

L.A.B. Flying Service's Piper Seneca made the first commercial revenue flight



using HITS in Juneau, Alaska, on Mar. 31. It followed an optimized area navigation (RNAV) route through airspace that would be inaccessible with conventional avionics.


The system was built by Chelton Flight Systems as part of the second

phase of the imaginative Capstone program, an FAA industry/academic partnership in Alaska. The cockpit employs a Chelton FlightLogic electronic flight information system-synthetic vision (EFIS-SV) using two glass displays, one for primary flight guidance and one for navigation.


The big innovation is the use of synthetic vision symbology to present information to pilots. The initial EFIS systems digitally replicated the rudimentary attitude and flight-director symbols of electro-mechanical instruments from an earlier era. Now, in addition to the flight path, pilots see a real-time 3D view of the terrain and obstacles on the primary flight display. These are complemented by a moving map on the navigation display and by aural terrain warnings.

Among the other "firsts" claimed by Capstone Phase II on the Juneau flight were the use of forward-looking 3D terrain and HUD symbology on a certified primary flight display, and commercial

Automatic Dependent Surveillance-Broadcast (ADS-B) equipment (*AW&ST* Sept. 18, 2000, p. 68). With GPS as the enabling technology, that phase indicated that a low-cost system could give bush pilots many of the safety benefits long-standard for commercial jet transports. The emphasis was on reducing controlled flight into terrain accidents for these pilots, who usually operate out of the range of navigation aids or radar help from ATC. Phase II with HITS and synthetic vision greatly expands those capabilities.



The navigation display shows GPS WAAS position and an approach not possible with conventional navigation aids due to a 20-30-deg. turn after the GASTN waypoint to align with the runway.



CAMI tested a four-axis side-arm controller in a simulator as a replacement for stick and throttle in a fly-by-wire performance control system.

use of the GPS wide-area augmentation system (WAAS).

Capstone has equipped three aircraft in Alaska with the Chelton Flight Systems' cockpit, and plans to outfit every commercial operator in SE Alaska within the next 18 months. The contract for 125 aircraft could expand to up to 200, according to Gordon Pratt, Chelton's president. The FAA is providing the equipment at no charge in Alaska to any commuter and on-demand (FAA Part 135) operator of fixed-wing aircraft or

The next major safety enhancement for GA aircraft could come from "performance control," according to Dennis B. Beringer, lead scientist for flight deck research at the FAA's Civil Aeromedical Institute (CAMI) in Oklahoma City. While known more for assisting FAA's Aircraft Certification Service and Flight Standards in defining requirements for both aircraft and pilots, CAMI is also an active partner in human factors research to improve cockpits.

With **performance control**, non-pilots could learn to fly *a simulator in 15 min.*

helicopters. A supplemental type certificate for helicopters was scheduled to be delivered on May 31. An additional 10 aircraft are being outfitted in the contiguous U.S., Pratt said, but at the expense of aircraft owners.

The first phase of the Capstone Program started as a demonstration that equipped a number of commuter and air taxi aircraft in the Yukon-Kuskokwim River delta area with a low-cost GPS, a terrain database, data link and

The performance-control concept was introduced in the 1970s, before electronics were sufficiently advanced for implementation. Beringer said that now some of the fly-by-wire military and commercial aircraft use what could be legitimately called performance-control logic, which not only make aircraft easier to fly, but can also add flight envelope protection.

With conventional flight controls, a pilot has direct command of the aero-

dynamic surfaces. With performance control, his movements would be transmitted via a fuzzy-logic controller to a flight management system or an auto pilot that would guide the aircraft to carry out the

desired performance goal. But unlike a simple autopilot, which directs a change in heading at a limited rate of turn, performance-control logic changes control laws so that a pilot commands the rate of turn and bank, and rate of climb or descent. It simplifies command of more complicated maneuvers, and is a compromise between automated maneuvering and manual flight control, Beringer said. Safety is further enhanced using a self-centering (spring-loaded) side stick which returns to the centered position when the pi-

lot relaxes pressure, thus bringing the aircraft to straight and level flight.

The reduced number of control movements is one reason flying is easier. Going into a turn with conventional controls, the pilot has to initiate the roll, and then neutralize the ailerons when he achieves the desired bank angle. But with performance controls, one movement establishes the desired bank angle/turn rate. One downside to performance control with envelope protection is the inability to do aerobatics, such as an aileron roll or loop, Beringer said.

In the four-axis side-arm controller (above), rotating the wrist governs the rate of turn, flexing the wrist vertically directs the rate of climb or descent, and fore and aft movement varies the airspeed. Interest in performance controls was renewed with NASA's Agate (Advanced General Aviation Transport Experiments) program, which was concerned with simplifying the flight task and reducing ab initio training requirements. Agate has also been a strong supporter of HITS.

Researchers had previously found that with performance control, non-pilots could learn to fly a simulator in 15 min. Beringer tested the system in a simula-

tor configured as a Piper Malibu at CAMI. It used HITS displays and a four-axis side-arm controller. Twenty-four individuals with varying flight experience participated: six high-flight-time pilots; six low-flight-time pilots; six student pilots, and six non-pilots. Each flight involved a takeoff into instrument conditions, a continuous climb while turning downwind, a turn to intercept the instrument landing system glidepath, and a descent to landing. Flights were divided between use of a conventional yoke and the side-arm controller.

The findings were consistent. The aircraft was more stable and had less variations in course and altitude using performance control than with conventional controls. Although experienced pilots

The **big** **innovation** is use of synthetic vision symbology

always outperformed less-experienced individuals, with either system, all agreed the effort required was nearly halved.

Performance control is not apt to be seen in Piper Cubs, but perhaps in Beech Bonanzas and Piper Malibus. A lot of them already have two- or three-axis autopilots, so a significant capability could be achieved by rigging a side-stick control to the autopilot, Beringer said.

But two large problems must be overcome for performance controls to appear in the next generation of GA aircraft. The first is cost. Affordable and certifiable computer controls and servos would have to drop to a level competitive with more conventional systems.

Second, a fly-by-wire debate must be resolved. Could an affordable system be built with sufficient reliability using triple- or quad-redundancy, or would a costly manual-reversion be required? A mechanical backup would add cost for installation and for training pilots to operate the two systems.

Complicating that issue is the question of the level of reliability required. The FAA's current standard for a flight-critical system is a failure rate of 10^{-9} . While this is a standard for NASA, it might not be reasonable for general aviation aircraft. Beringer points out that the failure rate for humans is about 10^{-3} . ●

Exhibit

2

Jed Margolin

From: "Jed Margolin" <jm@jmargolin.com>
To: <nasafoia@nasa.gov>
Sent: Saturday, June 28, 2008 7:05 PM
Attach: jm_nasa.pdf
Subject: FOIA Request

This request is made pursuant to the Freedom of Information Act.

I would like all documents related to the **Administrative Claim of Jed Margolin for Infringement of U.S. Patent Nos. 5,566,073 and 5,904,724; NASA Case No. I-222.**

I am attaching a letter dated June 11, 2003 from Alan Kennedy, Director, Infringement Division, Office of the Associate General Counsel as file *jm_nasa.pdf*. I provided the information requested, it was received by Mr. Kennedy, and thereafter Mr. Kennedy refused to respond to my attempts to find out the results of the investigation.

I believe NASA has had enough time to have completed its investigation by now.

Jed Margolin
1981 Empire Rd.
Reno, NV 89521-7430
775-847-7845
www.jmargolin.com

Exhibit

3

National Aeronautics and Space Administration
Headquarters
Washington, DC 20546-0001



August 5, 2008

Reply to Attn of: Office of the General Counsel

Mr. Jed Margolin
1981 Empire Road
Reno, NV 89521-7430

Re: Administrative Claim of Jed Margolin for Infringement of U.S. Patent
Nos. 5,566,073 and 5,904,724; NASA Case No. I-222.

Dear Mr. Margolin,

We are in receipt of the Freedom of Information Act Request (FOIA) conveyed to us by email dated June 30, 2008 in which you request copies of all documentation relating to your administrative claim of infringement of U.S. Patent Nos. 5,566,073 and 5,904,724.


We regret the delay in processing your claim and assure you that we are now undertaking measures to provide a resolution of your claim as soon as possible. Unfortunately, Mr. Alan Kennedy retired from NASA earlier this year and the action on your claim was not conveyed to management in a timely manner. In addition the local attorney responsible for review of your claim also departed from NASA. We are now cognizant of the importance of proceeding with a review of the claim and will contact you when we have reached a decision.

As to your FOIA request, as the investigation of your claim is ongoing, we kindly request that you allow us a 90 day extension to answer this request. Within that time period we should be able to obtain a better picture of our position vis-à-vis your claim and the request for documents may no longer be required.

We should inform you that we have received a separate communication from a company Optima Technology Group, claiming to have been assigned both of the patents in question. You informed me telephonically that this is the case; however, we have no record of any assignment of your patents to this firm and will need confirmation through appropriate attested documents delivered to the agency in order to recognize any claim of ownership by a party other than the inventor.

Thank you for your patience in this matter. Please contact the undersigned at (202) 358-0632 or email Jan.McNutt@nasa.gov if you have any additional questions or comments.

Sincerely,


Jan S. McNutt
Attorney-Advisor

Exhibit

4

Jed Margolin
Phone: 775-847-7845

1981 Empire Rd.
jm@jmargolin.com

Reno, NV 89521-7430
August 8, 2008

Mr. Jan S. McNutt
Office of the General Counsel
NASA Headquarters
Washington, DC 20546-0001

Re: FOIA Request (FOIA HQ 08-270) regarding NASA Case No. I-222

Dear Mr. McNutt,

As we discussed in our recent telephone conversations, my FOIA Request is entirely separate from NASA Claim Case I-222. The patents involved in the claim are now owned by Optima Technology Group, Inc. I trust that Optima Technology Group has now provided you with the documentation you requested in order to establish their ownership of the Patents.

I will agree to the 90 day extension you have requested for NASA to respond to my FOIA Request (HQ 08-270) if NASA acknowledges that my FOIA request is entirely separate from Optima Technology Group's Claim Case No. I-222.

Sincerely yours,



Jed Margolin

Exhibit

5

Jed Margolin
Phone: 775-847-7845

1981 Empire Rd.

Reno, NV 89521-7430
April 27, 2009

Mr. Christopher J. Scolese,
Acting Administrator, NASA
300 E Street, SW
Washington, DC 20546
(202) 358-2810 (Fax)

Dear Sir,

I sent you a letter by certified mail on April 6, 2009. According to USPS it has not been delivered. USPS has several theories:

1. They lost it;
2. NASA refused to accept delivery;
3. Something happened to it when it was sent to New Jersey to be irradiated.

I am appending the letter to this fax.

The letter asks you to confirm that I have exhausted all of the administrative remedies that NASA has to offer in my attempt to get NASA to comply with the Freedom of Information Act. Since it took me an hour this morning just to get a fax number for you -I was misdirected all around NASA- the answer is obviously, "Yes."

When I file suit against NASA in the U.S. District Court For the District of Nevada I had planned to mail the Complaint to you. Since it does not seem possible to mail anything to NASA with any hope of success, will you allow me to email or fax the Complaint to you and will you waive Service?

If you refuse, I will have to pay a process server to serve you. Then I will amend my Complaint to ask the Court to assess costs and punitive damages against NASA.

Sincerely yours,

Jed Margolin

Cc: Senator Harry Reid

Jed Margolin
Phone: 775-847-7845

1981 Empire Rd.

Reno, NV 89521-7430
April 6, 2009

Mr. Christopher J. Scolese,
Acting Administrator,
NASA
300 E. Street, SW
Washington, DC 20546

Dear Sir,

NASA has been acting in bad faith toward me for the past almost-6 years.

I am the named inventor on U.S. Patent 5,904,724 **Method and apparatus for remotely piloting an aircraft** issued May 18, 1999. This patent teaches the use of (what is now called) synthetic vision for controlling a UAV.

I contacted NASA in May 2003 after I became aware that NASA had used synthetic vision in the X-38 project. Because the use of synthetic vision for controlling a UAV can be used to the detriment of this country by unfriendly entities I wanted a friendly conversation because I thought NASA should buy the patent in order to control the technology

In June 2003 I was turned over to Mr. Alan Kennedy in the Office of the General Counsel. This is what I recorded in my Contact Log:

Summary: He basically said that what most independent inventors have is junk and that since I am an independent inventor what I have is probably junk. If NASA evaluates it as a license proffer it will give it a pro forma rejection and I will file a claim anyway, so the same people who rejected it as a proffer will reject it as a claim, but in the process will have had to do more work, so to save them some work they will ignore the proffer and handle it as a claim.

So, I filed a claim, completely answering all the questions on NASA's claim form. Then Mr. Kennedy informed me that NASA would conduct an investigation (expected to last 3-6 months) and that the purpose of the investigation would be to find prior art to invalidate the patent.

After six months I did not hear from NASA so I called Mr. Kennedy. He said:

1. The investigation had not been done.
2. NASA had a Research Exemption for using the patent. [Not true. See *Madey v. Duke* 307 F.3d 1351 (Fed. Cir. 2002)]
3. "The X-38 never flew." I informed him of the video on NASA's web site showing the X-38 flying.

4. The Statute of Limitations gives NASA 6 years to respond to my claim. (Wrong, it gives me 6 years to take NASA to Federal Claims Court.)
5. It would cost me more to sue NASA in Federal Claims Court than I could hope to recover from NASA.

After that, Mr. Kennedy refused to talk to me or respond to my letters. Then, various things came up and I was unable to pursue my claim against NASA.

Subsequently, I assigned the patent to Optima Technology Group, which has inherited the claim.

However, I still wanted to know what came up during the investigation so, on July 1, 2008 I filed a FOIA request. It was assigned FOIA HQ 08-270.

For some reason it was turned over to Mr. Jan McNut in the Office of the General Counsel.

His response is attached as *Reference 1*.

On August 5, 2008 Mr. McNut asked me to give NASA a 90-day extension to my FOIA request. I agreed.

In January, 2009 I received a letter from Mr. McNut who sent me back to the FOIA Office (*See Reference 2*), who wanted me to start over from scratch. Ms. Kelly Robinson then explained that she was currently working on FOIA requests filed two years before.

I told her that NASA did not get a do-over.

In the interests of brevity:

1. I talked to Ms. Robinson on March 18, 2009. She said she was sending me the results of the FOIA search, but there was some material she would not send me before it was internal Agency communications.
2. That was almost three weeks ago I have not received anything from NASA.

Therefore, Mr. Scolese, please confirm that I Have Exhausted All the Administrative Remedies that NASA Has to Offer. I need you to do this so I can bring suit against NASA in Federal Circuit Court.

If you fail to respond to this letter within ten days I will assume the answer is “Yes.”

And I will note your failure to respond in my upcoming article, “How NASA Defrauds Independent Inventors.” (That was not the title when this process started.) I will be sending the article to the various House and Senate oversight committees.

Sincerely yours,

Jed Margolin

Exhibit

6

Jed Margolin

From: "HQ-FOIA" <hq-foia@nasa.gov>
To: <jm@jmargolin.com>
Sent: Monday, May 18, 2009 12:30 PM
Attach: 2008-270.pdf; 08-270.DOC
Subject: FOIA 2008-270

FOIA 08-270

May 14, 2009

Mr. Jed Margolin
1981 Empire Road
Reno, NV 89521-7430
jm@jmargolin.com

Dear Mr. Margolin:

This is in response to your request received on June 30, 2008, pursuant to the Freedom of Information Act (FOIA) for *documents related to the Administrative Claim of Jed Margolin for infringement of U.S. Patent Nos. 5,566, 073 and 5,904,724; NASA Case No. I-222.*

The NASA Headquarters Office of the General Counsel conducted a search and from that search provided the enclosed documents responsive to your request.

It has been determined that portions of the records found responsive to your request contain information which is exempt from disclosure under the deliberative process privilege of Exemption 5. This privilege covers advisory opinions, recommendations, and deliberations, which are part of the government decision-making process, 5. U.S.C. §552(b)(5).

You may appeal this initial determination to the NASA Administrator. Your appeal must (1) be addressed to the Administrator, National Aeronautics and Space Administration, Washington, DC 20546, (2) be clearly identified on the envelope and in the letter as an "Appeal under the Freedom of Information Act", (3) include a copy of the request for the agency record and a copy of this initial adverse determination, (4) to the extent possible, state the reasons why you believe this initial determination should be reversed, and (5) be sent to the Administrator within thirty (30) calendar days of the receipt of this initial determination.

I apologize for the delay in processing your request. I appreciate your patience.

Sincerely,

Original Signed

Kellie N. Robinson
FOIA Public Liaison Officer
Headquarters
NASA
300 E Street, SW
Washington, DC 20546

Enclosures

From: McConnell, Stephen (HQ-NB000) [mailto:stephen.mcconnell-1@nasa.gov]
Sent: Tuesday, July 01, 2008 8:45 AM
To: foia@hq.nasa.gov
Cc: Robinson, Kellie N. (HQ-NB000)
Subject: FW: FOIA Request

From: Jed Margolin [mailto:jm@jmargolin.com]
Sent: Saturday, June 28, 2008 10:06 PM
To: nasafoia@nasa.gov
Subject: FOIA Request

This request is made pursuant to the Freedom of Information Act.

I would like all documents related to the **Administrative Claim of Jed Margolin for Infringement of U.S. Patent Nos. 5,566,073 and 5,904,724; NASA Case No. I-222.**

I am attaching a letter dated June 11, 2003 from Alan Kennedy, Director, Infringement Division, Office of the Associate General Counsel as file *jm_nasa.pdf*. I provided the information requested, it was received by Mr. Kennedy, and thereafter Mr. Kennedy refused to respond to my attempts to find out the results of the investigation.

I believe NASA has had enough time to have completed its investigation by now.

Jed Margolin
1981 Empire Rd.
Reno, NV 89521-7430
775-847-7845
www.jmargolin.com

Exhibit

7

National Aeronautics and Space Administration

Headquarters

Washington, DC 20546-0001



March 19, 2009

Reply to Attn of:

Office of the General Counsel

CERTIFIED MAIL

Dr. Robert Adams, CEO
Optima Technology Group
1981 Empire Road
Reno, NV 89521

RE: Administrative Claim for Infringement of US Patent No. 5,904,724;
NASA Case No. I-222

Dear Dr. Adams:

This letter concerns the above-identified administrative claim for patent infringement.

NASA received the initial notification of this claim in an email dated May 12, 2003, from Mr. Jed Margolin addressed to attorneys at the NASA Langley Research Center claiming that "NASA may have used one or more of [Mr. Margolin's] patents in connection with the X-38 project and may be using one or more of my patents in other projects using Synthetic Vision". Mr. Margolin identified two patents that he believed NASA may be infringing; the subject patent and Patent No. 5,566,073. On June 7, 2003, Mr. Margolin submitted his claim by fax to the NASA HQ attorney, Mr. Alan Kennedy. Mr. Kennedy responded by letter dated June 11, 2003 acknowledging the administrative claim and requesting that Mr. Margolin give a more detailed breakdown of the exact articles or processes that constitute the claim. Mr. Margolin responded by letter dated June 17, 2003, withdrawing his claim with regard to U.S. Patent No. 5,566,073, leaving the remaining claim for the subject patent. NASA is aware of the long pendency of this matter and we regret the delay.

On July 14, 2008 Optima Technology Group sent a letter addressed to Mr. Kennedy stating that they were the owners of the Jed Margolin patents due to an assignment and requesting that NASA now license the technology of the subject patent. With an email dated August 6, 2008 from Optima, NASA received a copy of a Patent Assignment, dated July 20, 2004, executed by Jed Margolin, the sole inventor on the subject patent, by which the entire right, title and interest in the patent has been assigned to Optima Technology Group, Inc. We previously noted in a letter dated August 20, 2008 from Mr. Jan McNutt of our office addressed to you that NASA believes there are certain irregularities surrounding this and collateral assignment documents associated with the subject patent. However, NASA will at this time forestall a detailed consideration of that issue. Instead, we will assume your *bona fides* in asserting that you are the legitimate owner of the subject patent and communicate

our findings directly with you. To the extent that Mr. Margolin has any interest in this matter, formally or informally, we will leave it up to you whether or not to communicate with him.

In light of the prior claim by Mr. Margolin, we consider your license proffer as an administrative claim of patent infringement. We turn now to the substance of your claim. In response to your initial letter dated July 14, 2008, Mr. McNutt's August 20, 2008 letter posed a number of questions, the purpose of which was to enable NASA to fully evaluate the details of your claim. Your organization failed to respond to these questions and, further, advanced the position that this matter does not involve a *new* claim (*Adams letter to McNutt, August 25, 2008*). We disagree that this is not a new claim. Nevertheless, NASA proceeds – in order to bring closure to this matter – on the basis that this claim centers around allegations that infringement arose from activities associated with NASA's X-38 Program, as advanced by Mr. Margolin. Accordingly, our investigation of this claim necessarily reflects the answers previously furnished by Mr. Margolin in response to NASA's June 11, 2003 letter to him containing substantially the same set of questions.

U.S. Patent No. 5,904,724 issued with twenty claims, claims 1 and 13 being the sole independent claims.

In order for an accused device to be found infringing, each and every limitation of the claim must be met by the accused device. To support a finding of literal infringement, each limitation of the claim must be met by the accused device exactly, any deviation from the claim precluding a finding of infringement. See *Lantech, Inc. v. Keip Mach. Co.*, 32 F.3d 542 (Fed. Cir. 1994). If an express claim limitation is absent from an accused product, there can be no literal infringement as a matter of law. See *Wolverine World Wide, Inc. v. Nike, Inc.*, 38 F.3d 1192, 1199 (Fed. Cir.1994).

In applying these legal precepts, reproduced below are the relevant portions of claims 1 and 13.

Claim 1. A system comprising:

* * *

a computer

* * *

said computer is. . .for *determining a delay time* for communicating said flight data between said computer and said remotely piloted aircraft, and wherein said computer adjusts the sensitivity of said set of one or more remote flight controls based on said delay time.
(emphasis added.)

Claim 13. A station for flying a remotely piloted aircraft that is real or simulated comprising:

* * *

a computer

* * *

said computer. . . to *determine a delay time* for communicating. . . flight control information between said computer and [a] remotely piloted aircraft, and said computer to adjust the sensitivity of [a] set of remote flight controls based on said delay time. . . (emphasis added.)

NASA has investigated activities surrounding the X-38 program at its Centers that conducted X-38 development efforts and has determined that no infringement has occurred. This result is compelled because none of NASA's X-38 implementations utilized a computer which is "for determining a delay time for communicating said flight data between said computer and said remotely piloted aircraft," as required by claim 1, nor a "computer . . . to determine a delay time for communicating . . . flight control information between said computer and [a] remotely piloted aircraft," as required by the limitations of claim 13.

Given that a computer which measures delay time is lacking from the NASA X-38 configuration, it follows that the NASA X-38 configuration had no "adjusting of the sensitivity of [a] set of one or more remote flight controls based on said delay time", as required in claim 1. Similarly, because the NASA X-38 configuration had no "computer to determine a delay time for communicating . . . flight control information between said computer and [a] remotely piloted aircraft, the configuration also had no adjusting of "the sensitivity of [a] set of remote flight controls based on said delay time", as called for by claim 13.

For at least the above-explained exemplary reasons, claims 1 and 13 have not been infringed. It is axiomatic that none of the dependent claims may be found infringed unless the claims from which they depend have been found to be infringed. *Wahpeton Canvas Co. v. Frontier, Inc.*, 870 F.2d 1546 (Fed. Cir. 1989). One who does not infringe an independent claim cannot infringe a claim dependent on, and thus containing all the limitations of, that claim. *Id.* Thus, none of claims 2-12 and 14-20 have been infringed.

NASA's X-38 development efforts ended in 2002. There may also be other features in NASA's X-38 development efforts that, upon further analysis, would reveal yet more recited claim limitations that are lacking in the NASA configuration related to those efforts.

We also note as a point of particular significance that the limitations included in claims 1 and 13 discussed above were added by amendment during the prosecution of the patent application. It is clear from an analysis of the patent application file wrapper history that the individual prosecuting the application stressed the importance of "the measurement of a communication delay in order to adjust the sensitivity of flight controls based on that delay." Also noted is the distinguishing arguments that these claims require that there be a "computer . . . located in the pilot station" and that "at least one real time measurement of the delay and some adjustment is contemplated." (See *Applicant's Amendment and Remark*, February 27, 1998 and *Response Under 37 C.F.R. § 1.116*, July 6, 1998). Clearly, the Patent Office Examiner allowed the application based on these prosecutorial arguments.

We have completed our investigation regarding the claim of patent infringement of U.S. Patent No. 5,904,724 and have determined that there is no patent infringement by, or

unauthorized use on behalf of, NASA. The above detailed discussion explains the basis for NASA's analysis and decision regarding the subject administrative claim.

As an aside, during NASA's investigation, numerous pieces of evidence were uncovered which would constitute anticipatory prior knowledge and prior art that was never considered by the U.S. Patent and Trademark Office during the prosecution of the application which matured into Patent No. 5,904,724. In view of the clear finding of lack of infringement of this patent, above, NASA has chosen to refrain from a discussion that would demonstrate, in addition to non-infringement, *supra*, invalidity of the subject patent. However, NASA reserves the right to introduce such evidence of invalidity in an appropriate venue, should the same become necessary.

This is a FINAL agency action and constitutes a DENIAL of the subject administrative claim for patent infringement.

Pursuant to 35 U.S.C. § 286, the statute of limitations for the filing of an action of patent infringement in the United States Court of Federal Claims is no longer tolled. Thus, any further appeal of this decision must be made by filing a claim for patent infringement in the United States Court of Federal Claims, pursuant to 28 U.S.C. § 1498(a).

Sincerely,



Gary G. Borda
Agency Counsel for Intellectual Property

Is your RETURN ADDRESS completed on the reverse side?

SENDER:

- Complete items 1 and/or 2 for additional services.
- Complete items 3, 4a, and 4b.
- Print your name and address on the reverse of this form so that we can return this card to you.
- Attach this form to the front of the mailpiece, or on the back if space does not permit.
- Write "Return Receipt Requested" on the mailpiece below the article number.
- The Return Receipt will show to whom the article was delivered and the date delivered.

I also wish to receive the following services (for an extra fee):

- Addressee's Address
- Restricted Delivery

Consult postmaster for fee.

3. Article Addressed to:
 DR. L. ADAMS CEO
 OPTIMA TECH GROUP
 1981 EMPIRE ROAD
 RENO, NV 89521

4a. Article Number: 7007 26800012216

4b. Service Type 4563

Registered Certified
 Express Mail Insured
 Return Receipt for Merchandise COD

7. Date of Delivery

5. Received By: (Print Name)


6. Signature: (Addressee or Agent)
 X

8. Addressee's Address (Only if requested and fee is paid)

PS Form 3811, December 1994 102595-98-B-0229 Domestic Return Receipt

Thank you for using Return Receipt Service.

7007 2680 0001 2216 4563



7007 2680 0001 2216 4563
 7007 2680 0001 2216 4563

U.S. Postal Service™
CERTIFIED MAIL™ RECEIPT
 (Domestic Mail Only; No Insurance Coverage Provided)

For delivery information visit our website at www.usps.com

OFFICIAL USE

Postage	\$	Postmark Here
Certified Fee		
Return Receipt Fee (Endorsement Required)		
Restricted Delivery Fee (Endorsement Required)		
Total Postage & Fees	\$	

Sent To: DR L ADAMS CEO
 Street, Apt. No., or PO Box No.: 1981 EMPIRE ROAD
 City, State, ZIP+4: RENO NV 89521

PS Form 3800, August 2006 See Reverse for Instructions

Exhibit

8

Jed Margolin
Phone: 775-847-7845

1981 Empire Rd.
Email: jm@jmargolin.com

Reno, NV 89521-7430
June 10, 2009

Administrator
NASA Headquarters
Washington, DC 20546

Appeal under the Freedom of Information Act to the NASA Response dated May 14, 2009 and received via email May 18, 2009.

Jed Margolin

FOIA 08-270

Filed: June 28, 2008

Sir:

This is an Appeal under the Freedom of Information Act to the NASA Response dated May 14, 2009 and received via email May 18, 2009 [*Appendix NA1 - NA65*] in FOIA Request 08-270 filed June 28, 2008 [*Appendix NA66*].

Because NASA's response was sent (and received) on May 18, 2009 this appeal is timely.

Summary

In its very tardy response to FOIA Request 08-270 by Jed Margolin ("Margolin") NASA withheld documents, citing *5 U.S.C. §552(b)(5)*.

One of the documents that NASA withheld from Margolin is a letter dated March 19, 2009 that was sent by Gary G. Borda ("Borda") NASA Agency Counsel for Intellectual Property to Optima Technology Group ("OTG"). (This document was given to Margolin by OTG.) In this letter Borda denies Claim I-222 regarding NASA's infringement of U.S. Patent 5,904,724 ('724) in the X-38 project.

Margolin's FOIA 08-270 request to NASA was to produce documents relating to Claim I-222 and NASA withheld the most material document so far.

The Borda letter asserts:

“... numerous pieces of evidence were uncovered which would constitute anticipatory prior knowledge and prior art that was never considered by the U.S. Patent and Trademark Office during the prosecution of the application which matured into Patent No. 5,904,724.”

And states, “... NASA reserves the right to introduce such evidence of invalidity in an appropriate venue, should the same become necessary.”

Circulating the patent report solely within NASA or among other federal agencies is not an appropriate venue for NASA to use to have a patent declared invalid. The only appropriate venues for NASA to challenge the validity of a U.S. Patent are in the U.S. Court of Federal Claims and the Court of Appeals for the Federal Circuit. A Court will not accept NASA’s word that a patent is invalid due to prior art; NASA would be required to produce the evidence.

Therefore, the exemption under *5 U.S.C. §552(b)(5)* does not apply.

The Borda letter also suggests the existence of other materials and/or documents, especially relating to whether NASA risked the X-38 by failing to provide compensation for the time delays in the synthetic vision flight control loop.

Details

Most of the documents NASA sent to Requestor Jed Margolin (“Margolin”) were documents Margolin already had, especially the documents Margolin had himself sent to NASA. There were other documents NASA admits to having but refused to provide [*Appendix NAI*]:

It has been determined that portions of the records found responsive to your request contain information which is exempt from disclosure under the deliberative process privilege of Exemption 5. This privilege covers advisory opinions, recommendations, and deliberations, which are part of the government decision-making process, 5. U.S.C.§552(b)(5).

The reference 5. U.S.C.§552(b)(5) states, referring to Section (a) which requires agencies to make information available to the public:

(b) This section does not apply to matters that are -

.

.

.

(5) inter-agency or intra-agency memorandums or letters which would not be available by law to a party other than an agency in litigation with the agency;

NASA did not give an *estimate* of the volume of the documents being withheld, in violation of 5 U.S.C.§552(a)(6)(F):

(F) In denying a request for records, in whole or in part, an agency shall make a reasonable effort to estimate the volume of any requested matter the provision of which is denied, and shall provide any such estimate to the person making the request, unless providing such estimate would harm an interest protected by the exemption in subsection (b) pursuant to which the denial is made.

And, since NASA did not give even a minimal description of the documents being withheld, that would probably have been the end of the matter. Without even a minimal description of the documents being withheld Margolin would have had no way of knowing if NASA was acting properly and in good faith.

NASA has a record of acting in bad faith toward Margolin. See:

1. Letter from Jed Margolin to Alan Kennedy (NASA Office of the General Counsel) dated January 6, 2004 confirming a portion of the telephone conversation Margolin had with Kennedy on December 10, 2003 [*Appendix NA72*]
2. Fax from Jed Margolin to Acting Administrator Scolese dated April 27, 2009 detailing NASA's almost-6 years of bad faith shown to Margolin. [*Appendix NA73*]

Note that neither document was included in NASA's Response to Margolin's FOIA Request, which suggests NASA withheld them in an attempt to avoid embarrassment to the Agency and for no other reason. *5 U.S.C. §552(b)* does not include "embarrassment to the agency" as a reason to withhold documents.

NASA is still acting in bad faith toward Margolin.

One of the documents that NASA withheld from Margolin is a letter dated March 19, 2009 that was sent by Gary G. Borda ("Borda") NASA Agency Counsel for Intellectual Property to Optima Technology Group ("OTG"). (This document was given to Margolin by OTG.) In this letter Borda denies Claim I-222 regarding NASA's infringement of U.S. Patent 5,904,724 ('724) in the X-38 project. [*Appendix NA80*]

Margolin's FOIA 08-270 request to NASA was to produce documents relating to Claim I-222 and NASA withheld the most material document so far.

The Borda letter is so important that it will be reproduced here in its entirety.

Dear Dr. Adams:

This letter concerns the above-identified administrative claim for patent infringement.

NASA received the initial notification of this claim in an email dated May 12, 2003, from Mr. Jed Margolin addressed to attorneys at the NASA Langley Research Center claiming that "NASA may have used one or more of [Mr. Margolin's] patents in connection with the X-38 project and may be using one or more of my patents in other projects using Synthetic Vision". Mr. Margolin identified two patents that he believed NASA may be infringing; the subject patent and Patent No. 5,566,073. On June 7, 2003, Mr. Margolin submitted his claim by fax to the NASA HQ attorney, Mr. Alan Kennedy. Mr. Kennedy responded by letter dated June 11, 2003 acknowledging the administrative claim and requesting that Mr. Margolin give a more detailed breakdown of the exact articles or processes that constitute the claim. Mr. Margolin responded by letter dated June 17, 2003, withdrawing his claim with regard to U.S. Patent No. 5,566,073, leaving the remaining claim for the subject patent. NASA is aware of the long pendency of this matter and we regret the delay.

On July 14, 2008 Optima Technology Group sent a letter addressed to Mr. Kennedy stating that they were the owners of the Jed Margolin patents due to an assignment and requesting that NASA now license the technology of the subject patent. With an email dated August 6, 2008 from Optima, NASA received a copy of a Patent Assignment, dated July 20, 2004, executed by Jed Margolin, the sole inventor on the subject patent, by which the entire right, title and interest in the patent has been assigned to Optima Technology Group, Inc. We previously noted in a letter dated August 20, 2008 from Mr. Jan McNutt of our office addressed to you that NASA believes there are certain irregularities surrounding this and collateral assignment documents associated with the subject patent. However, NASA will at this time forestall a detailed consideration of that issue. Instead, we will assume your *bona fides* in asserting that you are the legitimate owner of the subject patent and communicate

2

our findings directly with you. To the extent that Mr. Margolin has any interest in this matter, formally or informally, we will leave it up to you whether or not to communicate with him.

In light of the prior claim by Mr. Margolin, we consider your license proffer as an administrative claim of patent infringement. We turn now to the substance of your claim. In response to your initial letter dated July 14, 2008, Mr. McNutt's August 20, 2008 letter posed a number of questions, the purpose of which was to enable NASA to fully evaluate the details of your claim. Your organization failed to respond to these questions and, further, advanced the position that this matter does not involve a new claim (*Adams letter to McNutt, August 25, 2008*). We disagree that this is not a new claim. Nevertheless, NASA proceeds — in order to bring closure to this matter — on the basis that this claim centers around allegations that infringement arose from activities associated with NASA's X-38 Program, as advanced by Mr. Margolin. Accordingly, our investigation of this claim necessarily reflects the answers previously furnished by Mr. Margolin in response to NASA's June 11, 2003 letter to him containing substantially the same set of questions.

U.S. Patent No. 5,904,724 issued with twenty claims, claims 1 and 13 being the sole independent claims.

In order for an accused device to be found infringing, each and every limitation of the claim must be met by the accused device. To support a finding of literal infringement, each limitation of the claim must be met by the accused device exactly, any deviation from the claim precluding a finding of infringement. See *Lantech, Inc. v. Kelp Mach. Co.*, 32 F.3d 542 (Fed. Cir. 1994). If an express claim limitation is absent from an accused product, there can be no literal infringement as a matter of law. See *Wolverine World Wide, Inc. v. Nike, Inc.*, 38 F.3d 1192, 1199 (Fed. Cir.1994).

In applying these legal precepts, reproduced below are the relevant portions of claims 1 and 13.

Claim 1. A system comprising:

a computer

said computer is,.. for *determining a delay time* for communicating said flight data between said computer and said remotely piloted aircraft, and wherein said computer adjusts the sensitivity of said set of one or more remote flight controls based on said delay time. (emphasis added.)

Claim 13. A station for flying a remotely piloted aircraft that is real or simulated comprising:

a computer

3

said computer... to *determine a delay time* for communicating. . flight control information between said computer and [a] remotely piloted aircraft, and said computer to adjust the sensitivity of [a] set of remote flight controls based on said delay time. ... (emphasis added.)

NASA has investigated activities surrounding the X-38 program at its Centers that conducted X-38 development efforts and has determined that no infringement has occurred. This result is compelled because none of NASA's X-38 implementations utilized a computer which is "for determining a delay time for communicating said flight data between said computer and said remotely piloted aircraft," as required by claim 1, nor a "computer ... to determine a delay time for communicating ... flight control information between said computer and [a] remotely piloted aircraft," as required by the limitations of claim 13.

Given that a computer which measures delay time is lacking from the NASA X-38 configuration, it follows that the NASA X-38 configuration had no "adjusting of the sensitivity of [a] set of one or more remote flight controls based on said delay time", as required in claim 1. Similarly, because the NASA X-38 configuration had no "computer to determine a delay time for communicating ... flight control information between said computer and [a] remotely piloted aircraft, the configuration also had no adjusting of "the sensitivity of [a] set of remote flight controls based on said delay time", as called for by claim 13.

For at least the above-explained exemplary reasons, claims 1 and 13 have not been infringed. It is axiomatic that none of the dependent claims may be found infringed unless the claims from which they depend have been found to be infringed. *Wahpeton Canvas Co. v. Frontier, Inc.*, 870 F.2d 1546 (Fed. Cir. 1989). One who does not infringe an independent claim cannot infringe a claim dependent on, and thus containing all the limitations of, that claim. *Id.* Thus, none of claims 2-12 and 14-20 have been infringed.

NASA's X-38 development efforts ended in 2002. There may also be other features in NASA's X-38 development efforts that, upon further analysis, would reveal yet more recited claim limitations that are lacking in the NASA configuration related to those efforts.

We also note as a point of particular significance that the limitations included in claims 1 and 13 discussed above were added by amendment during the prosecution of the patent application. It is clear from an analysis of the patent application file wrapper history that the individual prosecuting the application stressed the importance of "the measurement of a communication delay in order to adjust the sensitivity of flight controls based on that delay." Also noted is the distinguishing arguments that these claims require that there be a "computer ... located in the pilot station" and that "at least one real time measurement of the delay and some adjustment is contemplated." (See *Applicant's Amendment and Remark*, February 27, 1998 and *Response Under 37 C.F.R. § 1.116*, July 6, 1998). Clearly, the Patent Office Examiner allowed the application based on these prosecutorial arguments.

We have completed our investigation regarding the claim of patent infringement of U.S. Patent No. 5,904,724 and have determined that there is no patent infringement by, or

4

unauthorized use on behalf of, NASA. The above detailed discussion explains the basis for NASA's analysis and decision regarding the subject administrative claim.

As an aside, during NASA's investigation, numerous pieces of evidence were uncovered which would constitute anticipatory prior knowledge and prior art that was never considered by the U.S. Patent and Trademark Office during the prosecution of the application which matured into Patent No. 5,904,724. In view of the clear finding of lack of infringement of this patent, above, NASA has chosen to refrain from a discussion that would demonstrate, in addition to non-infringement, *supra*, invalidity of the subject patent. However, NASA reserves the right to introduce such evidence of invalidity in an appropriate venue, should the same become necessary.

This is a FINAL agency action and constitutes a DENIAL of the subject administrative claim for patent infringement.

Pursuant to 35 U.S.C. § 286, the statute of limitations for the filing of an action of patent infringement in the United States Court of Federal Claims is no longer tolled. Thus, any further appeal of this decision must be made by filing a claim for patent infringement in the United States Court of Federal Claims, pursuant to 28 U.S.C. § 1498(a).

Sincerely,

Gary G. Borda
Agency Counsel for Intellectual Property

The Borda letter is not just a material document, it's a smoking gun.

1. Despite the documents supplied by OTG, and Margolin's confirmation in a telephone conversation with Jan McNutt (Office of the General Counsel), that OTG owns the subject patent, NASA continues to cast doubt on the legal ownership of the patent.

We previously noted in a letter dated August 20, 2008 from Mr. Jan McNutt of our office addressed to you that NASA believes there are certain irregularities surrounding this and collateral assignment documents associated with the subject patent.

2. NASA asserted it had found prior art to invalidate the patent.

As an aside, during NASA's investigation, numerous pieces of evidence were uncovered which would constitute anticipatory prior knowledge and prior art that was never considered by the U.S. Patent and Trademark Office during the prosecution of the application which matured into Patent No. 5,904,724. In view of the clear finding of lack of infringement of this patent, above, NASA has chosen to refrain from a discussion that would demonstrate, in addition to non-infringement, *supra*, invalidity of the subject patent. However, NASA reserves the right to introduce such evidence of invalidity in an appropriate venue, should the same become necessary.

In order to make this statement, NASA must have produced a patent report showing how each reference is directed to the claims in the '724 patent. This patent report is not exempt under *5 U.S.C. §552(b)(5)* because it is not "inter-agency or intra-agency memorandums or letters which would not be available by law to a party other than an agency in litigation with the agency;"

The reason it is not exempt is because "NASA reserves the right to introduce such evidence of invalidity in an appropriate venue, should the same become necessary."

Circulating the patent report solely within NASA or among other federal agencies is not an appropriate venue for NASA to use to have a patent declared invalid. The only appropriate venues for NASA to challenge the validity of a U.S. Patent are in the U.S. Court of Federal Claims and the Court of Appeals for the Federal Circuit. A Court will not accept NASA's word that a patent is invalid due to prior art; NASA would be required to produce the evidence.

Since this patent report is material under Margolin's FOIA Request and is not exempt under *5 U.S.C. §552(b)(5)* Margolin requests NASA immediately hand it over to him.

There is another reason NASA needs to hand over the patent report. Although Margolin no longer owns the '724 patent he is still the named inventor. By asserting it has evidence to invalidate the patent, and then withholding that evidence, NASA has defamed Margolin's reputation as an inventor. It also smacks of 1950s McCarthyism (making damaging accusations without providing proper evidence).

Margolin takes such attacks seriously. There is an article in the December 2008 issue of AUVSI's Unmanned Systems Magazine entitled **Synthetic Vision Technology for Unmanned Systems: Looking Back and Looking Forward** by Jeff Fox, Michael Abernathy, Mark Draper and Gloria Calhoun [*Appendix NB58*].

The article consists of a spurious history of synthetic vision. Many of the listed sources are from NASA, such as the HiMat project. [*Appendix NB8*] (While HiMat produced valuable results, it did not use synthetic vision.)

Margolin responded with the article **Synthetic Vision – The Real Story**. [*Appendix NBI*].

Although the editor of AUVSI Magazine had promised Margolin the opportunity to respond in the magazine, he later refused to even mention the controversy about the Abernathy article. [*Appendix NB60*]

NASA should be familiar with the name Mike Abernathy (Rapid Imaging Software). He provided the synthetic vision system for the X-38 project.

NASA should also be interested in the statements made on Abernathy's behalf in a letter from Abernathy's law firm to Optima Technology Group dated October 13, 2006. [*Appendix NA143*]

As you know, RIS creates computer software, and does not use or manufacture UAV systems or ground control stations. RIS software is used in UAVs to provide situation awareness for sensor operators. It is not used for piloting air vehicles. The sensor operator does not pilot the aircraft, and instead sits at a separate workstation operating a payload containing one or more cameras, which may be controlled using a joystick to point the camera package during search or tracking operations.

As you know, RIS refuses to allow its products to be used as a pilot aid, and RIS product licenses specifically prohibit use for piloting. None of RIS's customers use its software for piloting, for very good reason. Serious military regulations control placement of anything -synthetic vision included- on a pilot workstation. Before anything can be placed on the display in front of a pilot, it has to have met stringent criteria (MIL-STD 1787C, DO-178B, etc.), it must have been thoroughly ground tested, and it must have been fully flight tested. RIS software has never been through this process, and thus is prohibited from use for piloting. Accordingly, UAV manufacturers have purchased RIS products for use on the

sensor operator console, but none for the pilot console. This is a matter of Army doctrine and applies to Shadow, Warrior and Hunter.

Nor does RIS have its software in a form that would make it marketable for piloting. RIS software products are all based on the Microsoft Windows operating system. This offers many advantages, but is inappropriate to piloting aircraft because it is not a POSIX compliant real-time operating system. POSIX compliance is required by flight safety regulations. To create such a version would entail a one- to two-year conversion program in which RIS has not invested.

It is important to realize that the market for RIS products is quite different from the relaxed civilian world. If a military pilot chose to use synthetic vision in spite of military regulations or in defiance of a software license agreement, his career would be damaged or destroyed. Military pilots cherish their wings and would not consider risking them on something like synthetic version.

Finally, it appears from your correspondence that you regard research activities like NASA's X-38 prototypes (before the program was cancelled in 2002) as infringing the Margolin patents. This was not the case because of the claim limitations of the Margolin patents. However all RIS work for government agencies, including NASA, was authorized and consented to by the U.S. Government, and is protected under 28 U.S.C. §1498(a). As you are aware, any remedies you may have are against the government and are circumscribed by that statute and related law.

Although we need not discuss the invalidity of the Margolin patents given the above circumstances, you should be aware that both patents were anticipated by profound prior art dating back to 1977. If it should ever become necessary, we are confident that both would be held invalid.

(emphasis added)

He is asserting that Abernathy's synthetic vision software may not be used for piloting an aircraft, either remotely or with the pilot onboard. And yet, it was used for remotely piloting the X-38. [*Appendix NB20*]

From *Appendix NB21*:

On December 13th, 2001, Astronaut Ken Ham successfully flew the X-38 from a remote cockpit using LandForm VisualFlight as his primary situation awareness display in a flight test at Edwards Air Force Base, California. This simulates conditions of a real flight for the windowless spacecraft, which will eventually become NASA's Crew Return Vehicle for the ISS. We believe that this is the first test of a hybrid synthetic vision system which combines nose camera video with a LandForm synthetic vision display. Described by astronauts as "the best seat in the

house", the system will ultimately make space travel safer by providing situation awareness during the landing phase of flight.

Did NASA really trust the safety of an expensive test vehicle (X-38) to a synthetic vision system using Microsoft Windows?



To end this section, note that in 5 *U.S.C.* §552(f):

(f) For purposes of this section, the term—

(1) “agency” as defined in section 551 (1) of this title includes any executive department, military department, Government corporation, Government controlled corporation, or other establishment in the executive branch of the Government (including the Executive Office of the President), or any independent regulatory agency; and

(2) “record” and any other term used in this section in reference to information includes—

(A) any information that would be an agency record subject to the requirements of this section when maintained by an agency in any format, including an electronic format; and

(B) any information described under subparagraph (A) that is maintained for an agency by an entity under Government contract, for the purposes of records management.

Under this definition, neither Margolin nor Optima Technology Group (the owner of Claim I-222) is an “agency.” It also means that NASA is required to provide the records between NASA and Rapid Imaging Software (Mike Abernathy) which provided the synthetic vision system for the X-38 project which was referred to in the Borda letter.

3. The basis for NASA's rejection of Claim I-222 in the Borda letter is that the X-38 project did not implement one of the elements in the patent claims.

said computer is,.. for determining a delay time for communicating said flight data between said computer and said remotely piloted aircraft, and wherein said computer adjusts the sensitivity of said set of one or more remote flight controls based on said delay time. (emphasis added.)

To be precise, said computer does more than determine and compensate for time delays.

Claim 1 says:

1. A system comprising:

a remotely piloted aircraft including,

a position determining system to locate said remotely piloted aircraft's position in three dimensions; and

an orientation determining system for determining said remotely piloted aircraft's orientation in three dimensional space;

a communications system for communicating flight data between a computer and said remotely piloted aircraft, said flight data including said remotely piloted aircraft's position and orientation, said flight data also including flight control information for controlling said remotely piloted aircraft;

a digital database comprising terrain data;

said computer to access said terrain data according to said remotely piloted aircraft's position and to transform said terrain data to provide three dimensional projected image data according to said remotely piloted aircraft's orientation;

a display for displaying said three dimensional projected image data; and

a set of one or more remote flight controls coupled to said computer for inputting said flight control information, wherein said computer is also for determining a delay time for communicating said flight data between said computer and said remotely piloted aircraft, and wherein said computer adjusts the sensitivity of said set of one or more remote flight controls based on said delay time.

Claim 13 says:

13. A station for flying a remotely piloted aircraft that is real or simulated comprising:

a database comprising terrain data;

a set of remote flight controls for inputting flight control information;

a computer having a communications unit configured to receive status information identifying said remotely piloted aircraft's position and orientation in three dimensional space, said computer configured to access said terrain data according to said status information and configured to transform said terrain data to provide three dimensional projected image data representing said remotely piloted aircraft's environment, said computer coupled to said set of remote flight controls and said communications unit for transmitting said flight control information to control said remotely piloted aircraft, said computer also to determine a delay time for communicating said flight control information between said computer and said remotely piloted aircraft, and said computer to adjust the sensitivity of said set of remote flight controls based on said delay time; and

a display configured to display said three dimensional projected image data.

Is Borda saying that NASA did not determine and compensate for time delays in the X-38 synthetic vision flight control loop or simply that NASA did not use a computer to do so? If they did not use a computer, what did they use?

NASA is well aware of the problems caused by failing to compensate for time delays in flight control systems.

When a UAV is manually flown by a remote pilot, failure to compensate for delays in the communications link will lead to Pilot-Induced-Oscillation, which frequently leads to the loss of the aircraft.

This is a potential problem in Flight Control Systems even in aircraft with the pilot onboard.

The article **Fly-By-Wire - A Primer for Aviation Accident Investigators** (Air Line Pilot, February 2000, page 18 By F/O Steve Stowe (Delta), Local Air Safety Chairman, Delta Council 16) gives a basic explanation of the Control Systems Engineering analysis of the problem. From *Appendix NA87*:

Now for the bad news. While FBW technology could make an aerodynamically unstable aircraft flyable, it can also destabilize an otherwise stable airframe.

FBW flight control laws may not be stable for all values of gain or phase angle (the difference between pilot input and airplane response in terms of frequency; exactly opposite would be a 180-degree phase angle) that can be applied. Now costarring with static margin as stability factors are "gain margin" and "phase margin"-- measures of how much additional gain or phase-angle lag are available until the system becomes unstable. Computer simulation or flight testing can determine these two margins. But these data are often the manufacturer's proprietary information, so don't look for it on your weight-and-balance sheet.

Highly augmented aircraft, in which fly-by-wire transforms the basic aircraft aerodynamics, can exhibit cliff-like handling qualities.

“One reason is that fly-by-wire systems are susceptible to time delay, from a number of causes, which can seriously degrade the pilot's ability to control the aircraft. Time delay may vary for different sizes or frequencies of inputs. U.S. military standards suggest that time delays should be less than one tenth of a second for good handling qualities and that loss of control may occur with delays more than one quarter of a second (MIL STD 1797).”

(emphasis added)

Fly-By-Wire” means the aircraft surfaces are controlled through a computer instead of being controlled directly by the pilot.

From the same article [*Appendix NA92*]:

* **Time delay**--Delay from pilot input to FBW aircraft response. Caused by many factors including the effect of filters, computer processing time, task time-sharing by computers and signal processors, "higher order" effects of the feedback control system, digital sampling effects, and/or actuator rate limiting. Time delays of more than 0.25 second can cause enough lag to make the FBW aircraft unstable during certain tasks, especially in "high gain" situations.

(emphasis added)

There was a problem with Pilot-Induced-Oscillation during the development of the Space Shuttle. The following is from NASA Technical Memorandum NASA-TM-81366 **ANALYSIS OF A LONGITUDINAL PILOT-INDUCED OSCILLATION EXPERIENCED ON THE APPROACH AND LANDING TEST OF THE SPACE SHUTTLE** , Author: J. W. Smith, December 1981.

From the Introduction (*Appendix NA96*):

During the final free flight (FF-5) of the shuttle's approach and landing test (ALT) phase, the vehicle underwent pilot-induced oscillations (PIO's) near touchdown (refs. 1 to 3). The oscillations were present in both the pitch and roll axes and were initiated when the pilot made pitch controller inputs in an effort to control sink rate by changing pitch attitude. Because the control inputs were large and fairly rapid, the elevons rate limited in the pitch axis at the maximum priority rate limit set in the computers. The elevon rate limit also limits the vehicle's roll control capability, and this was partially responsible for the lateral control problem.

Several unpublished studies indicate that time delays as well as priority rate limiting were a significant factor in the PIO's. A simulator study of the effect of time delays on shuttle PIO's is reported in reference 4.

This report describes the combined effect of pilot input rate limiting and time delays. Frequency responses are predicted for various parameters under rate saturated conditions by using nonlinear analysis.

(emphasis added)

Note that the above references were for Flight Control Systems for aircraft with the pilot onboard. When an aircraft is flown manually through a communications link, the delays caused by the communications link become part of the flight control system.

From U.S. Patent 5,904,724 column 8, lines 14 – 36 [*Appendix NA142*]:

Flying an RPV is further complicated because there are additional time delays in the loop. The computer in the remote aircraft must first determine the aircraft's position and orientation. The additional processing for transmitting a secure signal by encryption and/or spread spectrum techniques may create additional delays. Transmission delay of signals between the remote aircraft and remote pilot station is negligible for a direct path. However, if the signals are relayed through other facilities the delay time may be appreciable, especially if an orbiting satellite is used. There are additional delays in the remote pilot station as the remote aircraft's position

and orientation are used to transform the data from the digital database to present the pilot with the synthesized 3D projected view from the remote aircraft. In one embodiment, the RPV system measures the various delays and modifies the control laws used by the computer in the remote pilot aircraft and in the feedback provided by the computer in the remote pilot station to the remote pilot. For example, the computer may adjust the sensitivity of the User Flight Controls 408 according to the delay (e.g., as the delay increases, the computer will decrease the sensitivity of the flight controls). The system also displays the measured delay to the remote pilot.

The issue of time delay in a UAV communications link was addressed in the literature by the Master's Thesis **Improving UAV Handling Qualities Using Time Delay Compensation** by Andrew J. Thurling (17 Sep 97-24 Feb 00, AIR FORCE INST OF TECH WRIGHT-PATTERSON AFB OH). From *Appendix NA139*:

Abstract

This study investigated control loop time delay and its effect on UAV handling qualities. Compensation techniques to improve handling qualities in the presence of varying amounts of time delay were developed and analyzed. One technique was selected and successfully flight-tested on a UAV.

Flight-testing occurred at a constant flight condition with varying levels of additional time delay introduced into the control loop. Research pilots performed a pitch tracking task and gave Cooper-Harper ratings and comments. Tracking errors were used as a quantitative measure of Pilot/Display/UAV system performance.

Predictive pitch compensation was found to significantly reduce pilot workload and improve Cooper-Harper ratings. Using the predictive display doubled the amount of system time delay that research pilots could tolerate while tracking the task bars. Overall system tracking performance, however, was not improved.

Parameter variations of +/- 20% in the aerodynamic model used to generate the predictive display produced statistically significant, although not operationally significant, changes in both pilot opinion and performance.

Analysis of flight test data and follow-on simulations resulted in predictor improvements that increased predictor accuracy to the point of restoring system tracking performance to equal that of the system with no additional time delay.

From *Appendix NA140*:

Preface

The effects of control system time delays on manned aircraft handling qualities are well understood. Unmanned aircraft have similar control, system delay, but have an additional latency caused by the datalink of the human operator's commands from control station to aircraft. The purpose of this thesis is to investigate the effects of time delay on the handling qualities of Unmanned Aerial Vehicles (UAV) and develop compensation strategies to mitigate the adverse effects of the delay. It is my hope that with techniques developed and investigated in this thesis future UAV operators will be able to employ UAVs from anywhere in the world thus increasing the flexibility of this already versatile platform.

(emphasis added)

And from the same report (*Appendix NA141*):

2.3.4 Time Delay Effects on Handling Qualities. Control difficulties during the 1977 Space Shuttle Approach and Landing Tests and YF-17 development resulted in efforts to investigate whether time delays associated with digital flight computers might be a contributing factor to the handling qualities problems. As discussed above, delays in flight control systems may come from a variety of sources. The effects of phase lag due to higher order effects, or analog time delay, had been studied (15) and were relatively well understood. A detailed study of the effects of pure delay, transport delay due to digital systems, had yet to be accomplished. In 1978 a NASA study employed an F-8 fighter aircraft modified with a digital flight control system to accomplish a detailed study of the effects of pure time delays on aircraft handling qualities (7, 4, 6). In 1979, Hodgkinson and others (29) conducted a study on the USAF/Calspan NT-33 inflight simulator in which they tested how mismatches between the higher order system and the LOES affected pilot opinion. They also investigated how well the delay term, e^{-sT} , in the LOES approximated the higher order phase lags and if the difference caused variations in pilot opinion. Both studies showed a strong correlation between pilot rating and the magnitude of the time delay, see Figures 2.8 and 2.10. The NT-33 data also showed that the degradation in pilot rating was similar for both digital transport delay and analog delay, or delay due to phase lag from higher order effects. The insidious nature of time delay's effects on handling qualities is demonstrated in a pilot comment during the F-8 research (7)

Pilots desire some response immediately upon stick input. It doesn't have to be much, but if he doesn't get response, his gains skyrocket.

The pilots in the NT-33 study also voiced similar concerns with delay after control inputs and the rapidity of the response following the delay. The authors of the F8 study (7) make a further observation that aircraft dynamics have an impact on system sensitivity to time delay.

(emphasis added)

So, is Borda saying that NASA did not determine and compensate for time delays in the X-38 synthetic vision flight control loop or simply that NASA did not use a computer to do so?

Which is it, because when a UAV is manually flown by a remote pilot, failure to compensate for delays in the communications link will lead to Pilot-Induced-Oscillation, which frequently leads to the loss of the aircraft.

Did NASA risk the X-38 by failing to provide compensation for the time delays in the synthetic vision flight control loop?

Conclusion

In its very tardy response to FOIA Request 08-270 by Jed Margolin (“Margolin”) NASA withheld documents, citing *5 U.S.C. §552(b)(5)*.

One of the documents that NASA withheld from Margolin is a letter dated March 19, 2009 that was sent by Gary G. Borda (“Borda”) NASA Agency Counsel for Intellectual Property to Optima Technology Group (“OTG”). (This document was given to Margolin by OTG.) In this letter Borda denies Claim I-222 regarding NASA’s infringement of U.S. Patent 5,904,724 (‘724) in the X-38 project.

Margolin’s FOIA 08-270 request to NASA was to produce documents relating to Claim I-222 and NASA withheld the most material document so far.

The Borda letter asserts:

“... numerous pieces of evidence were uncovered which would constitute anticipatory prior knowledge and prior art that was never considered by the U.S. Patent and Trademark Office during the prosecution of the application which matured into Patent No. 5,904,724.”

And states, “... NASA reserves the right to introduce such evidence of invalidity in an appropriate venue, should the same become necessary.”

Circulating the patent report solely within NASA or among other federal agencies is not an appropriate venue for NASA to use to have a patent declared invalid. The only appropriate venues for NASA to challenge the validity of a U.S. Patent are in the U.S. Court of Federal Claims and the Court of Appeals for the Federal Circuit. A Court will not accept NASA’s word that a patent is invalid due to prior art; NASA would be required to produce the evidence.

Therefore, the exemption under *5 U.S.C. §552(b)(5)* does not apply.

Margolin requests NASA produce the evidence that Borda refers to when he asserted:

“... numerous pieces of evidence were uncovered which would constitute anticipatory prior knowledge and prior art that was never considered by the U.S. Patent and Trademark Office during the prosecution of the application which matured into Patent No. 5,904,724.”

Margolin also requests that NASA show how such materials and/or documents are directed to the ‘724 claims.

And, finally, under 5 U.S.C. §552(f) NASA is required to provide the records between NASA and Rapid Imaging Software (Mike Abernathy) which provided the synthetic vision system for the X-38 project which was referred to in the Borda letter.

Respectfully,

Dated: June 10, 2009

/Jed Margolin/

Jed Margolin
1981 Empire Rd.
Reno, NV 89521-7430
775-847-7845
jm@jmargolin.com

Exhibit

9



Date: 06/12/2009

Jed Margolin:

The following is in response to your 06/11/2009 request for delivery information on your Express Mail(R) item number EQ98 5211 585U S. The delivery record shows that this item was delivered on 06/12/2009 at 07:08 AM in WASHINGTON, DC 20546 to T JACKSON. The scanned image of the recipient information is provided below.

Signature of Recipient:

Delivery Section	
Signature	
Printed Name	TERKY JACKSON

Address of Recipient:

Delivery Address	NASA 20546
------------------	------------

Thank you for selecting the Postal Service for your mailing needs. If you require additional assistance, please contact your local Post Office or postal representative.

Sincerely,

United States Postal Service

Exhibit

10

Jed Margolin
Phone: 775-847-7845

1981 Empire Rd.
Email: jm@jargolin.com

Reno, NV 89521-7430
July 21, 2009

Mr. Randolph Harris
NASA Office of the General Counsel
300 E St. SW
Washington, DC 20546
Phone: (202) 358-2450
Fax: (202) 358-2741
Email: randolph.harris-1@nasa.gov

Dear Mr. Harris.

As per our conversation today please confirm that NASA refuses to waive legal service unless the Complaint and Summons is sent to NASA by Certified USPS mail, and will not waive legal service if it is sent by USPS Express Mail.

As I explained during our conversation, I sent Acting Administrator Scolese a certified letter in April which USPS did not deliver, and which USPS could not find. Their explanation was that Certified Mail is only scanned into their tracking system when it is mailed and when it is delivered. If it is lost in transit it cannot be tracked.

In addition, according to USPS, Certified Mail is sent to New Jersey to be irradiated (delaying delivery and increasing the chances of being lost) while Express Mail is not.

As a result I do not consider Certified USPS mail to be a viable means of sending a Complaint and Summons to NASA.

If NASA refuses to waive service by Express Mail my only option will be to use a Process Server.

BTW, according to Rule 4 of the Federal Rules of Civil Procedure (December 1, 2008) it looks like I also have to serve:

1. The Attorney General of the United States, Washington, DC; and
2. The United States attorney for the district for the district where the action is brought. That would be The United States District Court, District of Nevada-Reno.

If this is correct, please give me the name and address for the United States attorney for the District of Nevada-Reno.

Sincerely yours,

/Jed Margolin/

Jed Margolin

Exhibit

11

Jed Margolin

From: "McNutt, Jan (HQ-MC000)" <jan.mcnutt@nasa.gov>
To: "Jed Margolin" <jm@jmargolin.com>
Sent: Friday, July 24, 2009 10:42 AM
Subject: FOIA Appeal of FOIA No. 2008-270

Dear Mr. Margolin,

I've been informed that you are in contact with Mr. Randolph Harris of our office concerning the subject FOIA appeal. I have been assigned to respond to your appeal and as it stands, we are now past due in our response to you. I apologize for the delay and am officially requesting an extension for NASA to respond to your FOIA appeal. I would like to ask for a 20 day extension from the action due date that I received, which was July 17, 2009, which would require us to provide you with a response by August 6, 2009. We have every intention of providing you with a proper response, but circumstances have been such that we have not been able to process the response in the allotted time.

Thank you for your consideration of an extension in this matter.

Regards,

*Jan S. McNutt
Senior Attorney (Commercial)
Office of the General Counsel
NASA Headquarters
Suite 9T11
300 E Street, SW
Washington, DC 20546-0001
(202) 358-0632
Jan.McNutt@nasa.gov*

Exhibit

12

Jed Margolin

From: "Jed Margolin" <jm@jmargolin.com>
To: "McNutt, Jan (HQ-MC000)" <jan.mcnutt@nasa.gov>
Sent: Friday, July 24, 2009 12:53 PM
Subject: Re: FOIA Appeal of FOIA No. 2008-270

Mr. McNutt,

You wrote:

> I've been informed that you are in contact with Mr. Randolph Harris of our office concerning the subject FOIA appeal. I have been assigned to respond to your appeal and as it stands, we are now past due in our response to you. I apologize for the delay and am officially requesting an extension for NASA to respond to your FOIA appeal. I would like to ask for a 20 day extension from the action due date that I received, which was July 17, 2009, which would require us to provide you with a response by August 6, 2009. We have every intention of providing you with a proper response, but circumstances have been such that we have not been able to process the response in the allotted time.

My response:

1. NASA failed to respond or ask for an extension within the 20 day statutory period.
2. NASA has been acting in bad faith toward me for the past six years and some months.
3. You have personally acted in bad faith toward me by taking improper advantage of (and my regretting) every courtesy I have ever extended to you.
4. When I asked Mr. Harris if NASA would accept Legal Service by Express Mail, he said, "No." Only by Certified Mail. I explained that when I sent NASA Certified Mail in April, the USPS failed to deliver it and was unable to determine how it was lost or where. As a result, I do not consider Certified Mail reliable and I will have to pay a process server to serve Administrator Bolden. Mr. Harris still said, "No."
5. Mr. Harris has failed to respond to my email (and later fax) asking him to confirm what he told me in our telephone conversation (that NASA will not accept Legal Service by Express Mail).
6. Mr. Harris said NASA's response to my FOIA Appeal will be to send me a bunch of documents, but he didn't know when. He guessed "7 days." Your characterization of NASA's response contains no promise of documents, only "a proper response."

And so, Mr. McNutt, my answer to you is "No."

Sincerely yours,

Jed Margolin

=====
----- Original Message -----

From: [McNutt, Jan \(HQ-MC000\)](#)

To: [Jed Margolin](#)

Sent: Friday, July 24, 2009 10:42 AM

Subject: FOIA Appeal of FOIA No. 2008-270

Dear Mr. Margolin,

I've been informed that you are in contact with Mr. Randolph Harris of our office concerning the subject FOIA appeal. I have been assigned to respond to your appeal and as it stands, we are now past due in our response to you. I apologize for the delay and am officially requesting an extension for NASA to respond to your FOIA appeal. I would like to ask for a 20 day extension from the action due date that I received, which was July 17, 2009, which would require us to provide you with a response by August 6, 2009. We have every intention of providing you with a proper response, but circumstances have been such that we have not been able to process the response in the allotted time.

Thank you for your consideration of an extension in this matter.

Regards,

*Jan S. McNutt
Senior Attorney (Commercial)
Office of the General Counsel
NASA Headquarters
Suite 9T11
300 E Street, SW
Washington, DC 20546-0001
(202) 358-0632
Jan.McNutt@nasa.gov*

Exhibit

13

Synthetic Vision Technology for Unmanned Aerial Systems: Looking Back and Looking Forward

By Jeff Fox, Michael Abernathy, Mark Draper and Gloria Calhoun

Using computers and terrain databases to generate a simulated, real-time, three-dimensional view of an environment—otherwise known as synthetic vision—has been applied to unmanned aircraft systems for three decades.


More recently it has evolved away from being a piloting aid to a potentially powerful tool for sensor operators. Technology observers expect it can help offset many factors that currently compromise the usefulness of UAS video imagery: narrow camera field of view, degraded datalinks, poor environmental conditions, limited bandwidth and highly cluttered visual scenes such as those found in urban areas.

With synthetic vision technology, information can be pulled from databases (of terrain elevation, cultural features, maps, photo imagery) and combined with data from networked sources, all of which can be represented as computer-generated imagery and symbology and overlaid on a dynamic video image display. The imagery and symbology appears to coexist with real objects in the scene, allowing an operator to cut through the clutter and maintain situational awareness of the environment.

There is a large body of research from the 1970s to the present that addresses the application of synthetic vision to manned and unmanned aircraft. In the interest of brevity, this article will focus on select systems that were important enablers toward UAS synthetic vision systems.

The story begins in the 1970s when the use of computers to create 3D real-time, out-the-window synthetic environments was beginning to see wide acceptance for training pilots of manned aircraft. Computer graphics company Evans and Sutherland (E&S), of Salt Lake City, Utah, had seen the commercial potential for flight simulation and had introduced special-purpose graphics computers, like their Picture System, which transformed and projected 3D terrain data as simple 3D polygons to a pilot's perspective view in real-time. In 1975, an engineering student named Bruce Artwick wrote "Flight Simulator" for the Apple II computer. He formed a company and in 1980 marketed the product that ultimately became Microsoft Flight Simulator.

This emergence of computer flight simulation in the 1970s appears to have sparked a monumental amount of research. The U.S. Air Force began its Visually Coupled Airborne Systems Simulator (VCASS) program, with a particular eye toward future-generation fighter aircraft ("VCASS: An Approach to Visual Simulation," Kocian, D., 1977). NASA was developing synthetic vision for the Super Sonic Transport and for its High Maneuverability Aircraft



NASA's HiMAT remotely piloted vehicle after flight at Dryden Flight Research Center. Photo courtesy of NASA.

Testbed (HiMAT) remotely piloted vehicle (RPV) program. Educational institutions studied the limitless new possibilities for virtual reality human-machine interfaces. By the mid-1980s, synthetic vision for RPV simulation was even commercially available for radio control aircraft hobbyists.

In 1977, NASA researcher Charles Knox published "Pathway-in-the-Sky Contact Analog Piloting Display," which included a complete design for a synthetic vision system. It featured a computer that projected a 3D view of the terrain given an aircraft's position and orientation. This out-the-window perspective view was displayed on a CRT type display. Such displays were called "Pictorial Format" avionics systems, but we recognize them as containing all of the essential elements of a modern synthetic vision display.

In 1979, the U.S. Air Force completed its "Airborne Electronic Terrain Map Applications Study" and in 1981 published "The Electronic Terrain Map: A New Avionics Integrator" describing how a computerized terrain database could be displayed as an out-the-window 3D view allowing the pilot to "see" even at night and in other limited visibility situations.

Also in 1979, the Air Force published research identifying human factors problems that would have to be overcome in RPV cockpit design ("Visual-Proprioceptive Cue Conflicts in the Control of Remotely Piloted Vehicles" by Reed in 1977). NASA would use this in the design of the HiMAT RPV 3D visual system in 1984.

Pictorial format avionics (i.e., synthetic vision) formed a key ingredient of the Air Force Super Cockpit concept. This program included a bold future vision in which "the pilot need not be present in the actual vehicle which he is piloting since with the appropriate data links a 'remote' super cockpit would provide the visual and aural 'telepresence' cues as if he were located in the vehicle," according to Air Force researcher Tom Furness.


CONTINUED ON PAGE 28

HiMAT: RPV with Synthetic Vision

In 1984, NASA researcher Shahan Sarraffian published research that investigated synthetic vision for lateral control during RPV landings. These tests featured the HiMAT vehicle, flown at Dryden Flight Research Center. These aircraft were dropped from a B-52 and remotely piloted from a ground station to a landing on the lakebed. The vehicle had a nose camera which produced video that could be shown in the remote cockpit, allowing the comparison of nose camera imagery versus synthetic vision during pilot testing.

Vehicle position was computed using radar computations along with a radio altimeter. Electro-mechanical gyroscope systems were installed onboard the aircraft and measured the three-dimensional attitude of the vehicle. The position and attitude were down-linked from the aircraft to a remote cockpit, and pilot control inputs were up-linked from the remote cockpit via the radio communication system.

The remote cockpit included a joystick and rudder controls connected to the computer and control signals were uplinked to the UAV. The computer compensated for delays in the control/communications loop.



The HiMAT RPV remote cockpit showing synthetic vision display. Photo courtesy of NASA.

The Edwards Air Force Base dry lake bed and runway were represented in three dimensions in the terrain database as polygons (triangles and rectangles). An E&S Picture System computer transformed the terrain in the database into a projected 3D out-the-window view at the pilot cockpit. Finally, the projected 3D view was displayed on an E&S Calligraphic video display system capable of 4000 lines of resolution. According to the pilots participating in the study, the synthetic vision compared well to the nose camera view. By the mid 1990s, NASA had migrated the RPV synthetic vision concept used on HiMAT to PC computers for the X-36 and X-38 flight demonstration vehicles.

One of the early uses of synthetic vision for UAVs—then most often called RPVs—was recreational simulation. In 1986, Ambrosia Microcomputer Products of Willowbrook, Ill., introduced RC AeroChopper, a radio controlled aircraft simulator which enabled pilots to learn to fly a remotely controlled aircraft, without risk to their actual vehicle. According to the “AeroChopper Owner’s Manual” (Stern, 1986), the product accepted aileron, elevator, rudder, and throttle pilot inputs via joysticks to control the simulated aircraft. The product also contained data files containing a 3D terrain database provided with AeroChopper representing the earth’s surface as well as buildings and obstructions.

The software was run on a computer (an Amiga for example) and was connected to the flight controls and communicated the aircraft position and attitude to the user. The computer used the terrain data to create a projected view of the aircraft and its environment in three dimensions. Like most visual simulations of its time, the program used relatively few polygons to represent the terrain and man-made objects and so looks crude by today’s standards.

Synthetic Vision for Sensor Operations

Although most of the historical focus with synthetic vision has been on aiding flight management, recent efforts have focused on how synthetic vision can aid UAS sensor operator functions.

Ongoing research at the U.S. Air Force Research Laboratory’s Human Effectiveness Directorate is exploring how to improve the usefulness of video imagery to UAS sensor operators. The overall objective is to determine the value of combining synthetic vision imagery/symbology with live camera video presented on a UAS control station camera display.

One research study evaluated the utility of computer-generated video overlays for four different task types: controlling the camera to locate specific ground landmarks in the 360 degree area surrounding the loitering UAV; designating multiple ground targets marked with synthetic symbology; tracing a synthetically highlighted ground convoy route with the UAV camera boresight; and reading text from synthetic overlaid symbology.

The UAS telemetry update rate was manipulated from 0.5 Hz to 24 Hz. The results indicated the potential of synthetic symbology overlay for enhancing situation awareness, reducing workload and improving the designation of points of interest at nearly all the update rates evaluated and for all four task types. However, data across the task types indicated that update rates greater than 2-4 Hz generally resulted in improved objective performance and a subjective sense that the symbology was useful.

A second research area focused on a picture-in-picture (PIP) concept where video imagery is surrounded by a synthetic-generated terrain imagery border on the physical camera display, increasing the operator’s instantaneous field-of-view. Experimental data showed that the PIP helps mitigate the “soda-straw effect,” reducing landmark search time and enhancing operator situation awareness. In an evaluation examining the impact of PIP display size and symbology overlay registration errors, results indicated that performance on a landmark search task was particularly better with the more compressed video imagery, reducing average designation time by 60 percent. Also, the registration error between the virtual flags and their respective physical correlates was less critical with the PIP capability enabled. The details were published in “Picture-in-Picture Augmentation of UAV Workstation Video Display” by Gloria Calhoun and others in 2007.

The recent availability of sophisticated UAS autopilots capable of autonomous flight control has fundamentally changed the paradigm of UAS operation, potentially reducing the usefulness of synthetic vision for supporting UAS piloting tasks. At the same time, research has demonstrated and quantified a substantial improvement in the efficiency of sensor operations through the use of synthetic vision sensor fusion technology. We expect this to continue to be an important technology for UAS operation.

Jeff Fox is Flight Operations Engineer at NASA Johnson Space Center. Michael Abernathy is Director of Development with Rapid Imaging Software, Inc. Mark Draper and Gloria Calhoun are Senior Research Scientists at the Air Force Research Laboratory, Wright-Patterson Air Force Base, Ohio.

Exhibit

14

Synthetic Vision Technology for Unmanned Aerial Systems: The Real Story

By Jed Margolin
January 7, 2009

Contents

[Introduction](#)

[What is Synthetic Vision?](#)

[Digital Terrain Elevation Database](#)

[Displaying the Digital Elevation Database](#)

[NASA HiMAT](#)

[Visual-Proprioceptive Cue Conflicts in the Control of Remotely Piloted Vehicles, Reed, 1977](#)

[Simulators](#)

[When Did NASA Start Working on Synthetic Vision?](#)

[Other References cited by the AUVSI Authors](#)

["Pathway-in-the-Sky Contact Analog Piloting Display," Knox and Leavitt, 1977](#)

["The Electronic Terrain Map: A New Avionics Integrator", Small, D.M., 1981](#)

["VCASS: An Approach to Visual Simulation," Kocian, 1977](#)

[U.S. Patent 5,566,073 **Pilot Aid Using A Synthetic Environment** issued October 15, 1996 to Margolin](#)

[U.S. Patent 5,904,724 **Method and apparatus for remotely piloting an aircraft** issued May 18, 1999 to Margolin](#)

[U.S. Patent Application Publication 20080033604 **System and Method For Safely Flying Unmanned Aerial Vehicles in Civilian Airspace**](#)

[The Future of Synthetic Vision](#)

[References](#)

Introduction

This is in response to the article **Synthetic Vision Technology for Unmanned Systems: Looking Back and Looking Forward** by Jeff Fox, Michael Abernathy, Mark Draper and Gloria Calhoun which appeared in the December 2008 issue of AUVSI's Unmanned Systems (page 27). [{Ref. 1}](#)

The AUVSI Authors have used the term "synthetic vision" so loosely that many readers will believe it was invented long before it actually was. This is an important issue. Aerospace is a field where precision and accuracy is critical. There are also patent rights involved. In the interests of full disclosure I am the listed inventor on several patents relating to synthetic vision and there is a patent infringement disagreement between the owner of the patents (Optima Technology Group) and the company that one of the AUVSI Authors is affiliated with (Rapid Imaging Software).

What Is Synthetic Vision?

The term "Synthetic Vision" originally meant anything that you put up on a video display.

For example, there is U.S. Patent 5,593,114 **Synthetic Vision Automatic Landing System** issued January 14, 1997 to Ruhl (Assignee McDonnell Douglas Corporation). [{Ref. 2}](#)

From Column 2, lines 16 - 27:

The instant invention is an Enhanced or Synthetic Vision (also called Autonomous) Landing System (E/SV). This system allows the pilot to view the approach scene with the use of a forward looking radar or equivalent sensor which provides the means of identifying the runways and the airport and land the aircraft using the automatic landing systems on virtually all types of aircraft. A pilot effectively turns the flight task during zero visibility or other low visibility weather conditions into a synthetic "see to land" approach because the image from the forward looking sensor provides sufficient detail to turn any instrument landing into what appears to be a visual landing.

In this patent Enhanced or Synthetic Vision is a display of the data from a forward looking radar or equivalent sensor.

This was also the FAA's definition at the time, in their **Synthetic Vision Technology Demonstration, Volume 1 of 4, Executive Summary** [{Ref 3}](#). From PDF page 10:

1.1 BACKGROUND

In 1988 the Federal Aviation Administration (FAA), in cooperation with industry, the United States Air Force (USAF), the Navy, and several other government organizations initiated an effort to demonstrate the capabilities of existing technologies to provide an image of the runway and surrounding environment for pilots operating aircraft in low visibility conditions. This effort was named the Synthetic Vision Technology Demonstration (SVTD) program. Its goal was to document and demonstrate aircraft sensor and system performance achieved with pilots using millimeter wave (MMW) radar sensors, a forward-looking infrared (FLIR) sensor, and a head-up display (HUD).

And from PDF pages 11,12:

1.2. OBJECTIVE

The objective of the Synthetic Vision Technology Demonstration program was to develop, demonstrate, and document the performance of a low-visibility, visual-imaging aircraft landing system. The experimental Synthetic Vision System components included on-board imaging sensor systems using millimeter-wave and infrared technology to penetrate fog, and both head-up (HUD) and head-down (HDD) displays. The displays presented the processed raster image of the forward scene, combined with suitable avionics-based stroke symbology for the pilot's use during a manually flown approach and landing. The experimental system, sometimes referred to as a functional prototype system, included all the functions (in prototype form only) required to accomplish precision, non-precision, and non-instrument approaches and landings in low visibility weather conditions.

In the AUVSI Authors' own article they equate "pictorial format avionics" with "synthetic vision." [Paragraph 10]:

Pictorial format avionics (i.e., synthetic vision) formed a key ingredient of the Air Force Super Cockpit concept.

Boeing's report **Multi-Crew Pictorial Format Display Evaluation** [{Ref. 4}](#) describes what Pictorial Format means (PDF Page 17):

The Multi-Crew Pictorial format Display Evaluation Program is the third in a series of contracted efforts, sponsored primarily by the Air Force Flight Dynamics Laboratory, Crew Systems Development Branch, (AFWAL/FIGR). In the first of these efforts, conceptual displays were developed for six primary fighter crew station functions: primary flight, tactical situation, stores management, systems status, engine status, and emergency procedures (Jauer and Quinn, 1982).

In the second contract, Pictorial Format Display Evaluation (PFDE), the Boeing Military Airplane Company continued the development beyond the paper formats of the earlier program and implemented the results in a piloted simulation. Two simulation studies were conducted to evaluate the usability and acceptability of pictorial format displays for single-seat fighter aircraft; to determine whether usability and acceptability were affected by display mode -- color or monochrome; and to recommend format changes based on the simulations. In the first of the two PFDE studies, pictorial formats were implemented and evaluated for flight, tactical situation, system status, engine status, stores management, and emergency status displays. The second PFDE study concentrated on the depiction of threat data. The number of threats and the amount and type of threat information were increased. Both PFDE studies were reported in Way, Hornsby, Gilmour, Edwards and Hobbs, 1984.

Pictorial Format Avionics is pictures. That explains why it is called **Pictorial** Format Avionics.

Why can't we use the term "Synthetic Vision" to mean anything we want it to mean?

1. It is sloppy.
2. The FAA has a definition for "Synthetic Vision" and if you want an FAA type certificate for your Synthetic Vision product you have to use their definition.

[{Ref. 5 – FAA current definition of synthetic vision}](#)

Synthetic vision means a computer-generated image of the external scene topography from the perspective of the flight deck that is derived from aircraft attitude, high-precision navigation solution, and database of terrain, obstacles and relevant cultural features.

{Emphasis added}

[{Ref. 6 – FAA Synthetic Vision is based on a Digital Elevation Database}](#)

“Everyone gets their data from the same original source.”

“If accuracy of data base must be validated then SV is unapproveable.”

“Current resolution tends to round-up the elevation data so that small errors are not as significant and on the conservative side.”

{Emphasis added}

Therefore, Synthetic Vision means a computer-generated image of the external scene topography from the perspective of the flight deck that is derived from aircraft attitude, high-precision navigation solution, and digital terrain elevation database, obstacles and relevant cultural features.

Implicit in this is that in order for the external scene topography to be viewed from the perspective of the flight deck it has to be a 3D projected view and that the digital terrain elevation database must represent real terrestrial terrain, as opposed to terrain that is simply made up.

Digital Terrain Elevation Database

The **Digital Terrain Elevation Database** is also called the **Digital Elevation Database** or **Digital Elevation Model**. From [Ref. 7](#):


The USGS Digital Elevation Model (DEM) data files are digital representations of cartographic information in a raster form. DEMs consist of a sampled array of elevations for a number of ground positions at regularly spaced intervals. These digital cartographic/geographic data files are produced by the U.S. Geological Survey (USGS) as part of the National Mapping Program and are sold in 7.5-minute, 15-minute, 2-arc-second (also known as 30-minute), and 1-degree units. The 7.5- and 15-minute DEMs are included in the large scale category while 2-arc-second DEMs fall within the intermediate scale category and 1-degree DEMs fall within the small scale category - (Source: USGS)

The Digital Elevation Model was substantially improved by STS-99 when Endeavour's international crew of seven spent 11 days in orbit during February 2000 mapping the Earth's surface with radar instruments. [{Ref. 8}](#)


Displaying the Digital Elevation Database

Now that we have a Digital Elevation Database consisting of a sampled array of elevations for a number of ground positions at regularly spaced intervals, what do we do with it? The database is just elevation points.

If you display only points there is no way to remove "hidden points" because there are no surfaces to test them against. (Things can only be hidden behind surfaces.) The result is a jumble which looks like this (the only useful features are the highest peaks):



This following picture shows the same scene rendered in polygons. (The polygons are crude because I had only a few colors to work with and there is no clipping, only polygon sorting):



After you have used the digital elevation points to produce polygons you can shade and blend the polygons so that the underlying polygons may no longer be obvious. Honeywell did an excellent job in their IPFD (Instrument Primary Flight Display) [\[Ref. 9\]](#):



NASA HiMAT

The AUVSI Authors have gone to considerable lengths to persuade readers that NASA's HiMAT project was Synthetic Vision [Paragraphs 11 – 14]. It wasn't.

HiMAT - Summary

Sarrafiian ([Ref. 11](#))

1. "The vehicle was flown with cockpit display instruments until the landing approach phase of the flight when the camera aboard the aircraft was activated to provide the pilot with a television display during the approach."
2. During the operational phase of the HiMAT program, a simulator was used to adjust the control laws for the primary control system. The display presented to the pilot of this simulated system was a display of an instrument landing system (ILS).
3. Separately, a study was undertaken to compare evaluations of pilots using a simulated visual display of the runway scene and a simulated ILS display with the results of actual flight tests, using the HiMAT aircraft as a representative remotely piloted research vehicle.

There is no mention of a terrain database or any suggestion that the simulated visual display of the runway scene was ever used to control a real aircraft. It was never anything other than a simulation.

From Evans and Schilling {Ref. 13}:

Visual Landing Aid

Actual. - Cues to the pilot during landing included the cockpit instruments, ILS/glideslope error indicators, television transmission from the vehicle, calls on the radio from the chase pilot, and space-positioning calls from the flight-test engineer.

Simulation model. - For most of the program, the landing cues for the pilot in a HiMAT simulation included only the instruments, mapboards, and the ILS/glideslope error indicators. Although these are all valid cues, they could not achieve the same effect as the television transmission used in actual flight. During flight, as soon as the pilot can identify the runway, his scan focuses more on the television picture and less on the cockpit instruments. To help alleviate this lack of fidelity in the simulation, a display of the runways on the dry lakebed was developed on a recently purchased Evans and Sutherland Graphics System.

HiMAT Details

From NASA's description of the HiMAT project [{Ref. 10}](#):

Highly Maneuverable Aircraft Technology

From mid-1979 to January 1983, two remotely piloted, experimental Highly Maneuverable Aircraft Technology (HiMAT) vehicles were used at the NASA Dryden Flight Research Center at Edwards, Calif., to develop high-performance fighter technologies that would be applied to later aircraft. Each aircraft was approximately half the size of an F-16 and had nearly twice the fighter's turning capability.

and, later:

The small aircraft were launched from NASA's B-52 carrier plane at an altitude of approximately 45,000 feet. Each HiMAT plane had a digital on-board computer system and was flown remotely by a NASA research pilot from a ground station with the aid of a television camera mounted in the cockpit. There was also a TF-104G chase aircraft with backup controls if the remote pilot lost ground control.

NASA's article says it was flown remotely by a pilot using a television camera in the aircraft. It does not say it was flown using what is now known as synthetic vision. (As previously explained, the definition of the term "synthetic vision" has changed over the years.)

It does say:

Dryden engineers and pilots tested the control laws for the system, developed by the contractor, in a simulation facility and then in flight, adjusting them to make the system work as intended.

and that is where the AUVSI Authors have gone astray, whether deliberately or through poor scholarship.

The AUVSI Authors cite the report by Shahan Sarrafian, "**Simulator Evaluation of a Remotely Piloted Vehicle Lateral Landing Task Using a Visual Display.**" There are two Sarrafian reports with that title, one dated May 1984; the other dated August 1984. See [Ref. 11](#) which contains links to the reports as well as to mirrored copies. The August 1984 report has been converted to text to make it easy to search and to quote from.

The title of the Sarrafian report gives an accurate description of his project, "**Simulator Evaluation of a Remotely Piloted Vehicle Lateral Landing Task Using a Visual Display.**"

It was a simulation.

Here is the Introduction from the report. It's a little long but it describes the heart of the matter. I have underlined the parts that are especially relevant.

Introduction

The remotely piloted research vehicle (RPRV) is a tool that can be used for exploring unproven and advanced technologies without risking the life of a pilot. The flight testing of RPRVs(l) allows programs to be conducted at a low cost, in quick response to demand, or when hazardous testing is required to assure the safety of manned vehicles. Yet this type of testing must be performed by the most versatile

system available - the pilot. The pilot has the same responsibilities and tasks as if he were onboard the aircraft; this includes guiding the vehicle to a safe landing. The only difference is that he must accomplish this final task from a ground-based cockpit.

The highly maneuverable aircraft technology (HiMAT) aircraft (Fig. 1) is a remotely piloted research vehicle that has completed flight tests to demonstrate advanced fighter technologies at NASA Ames Research Center's Dryden Flight Research Facility. The HiMAT vehicle is a 0.44-scale version of an envisioned small, single-seat fighter airplane. The mission profile of HiMAT (Fig. 2) included a launch from a B-52 aircraft and the acquisition of flight test data. The vehicle was then flown by a NASA test pilot in a fixed ground-based cockpit to a horizontal landing on the Edwards dry lakebed. The vehicle was flown with cockpit display instruments until the landing approach phase of the flight when the camera aboard the aircraft was activated to provide the pilot with a television display during the approach.

During the operational phase of the HiMAT program, the lateral-stick gearing gain used in the aircraft approach was altered from a variable gain schedule (derived from simulation) to a constant gain schedule. The schedules were changed in response to pilot complaints about oversensitivity in the lateral stick that required high pilot compensation. Before the modified gain schedule was implemented into the primary control system (PCS), it was evaluated in the HiMAT simulator using an instrument landing system (ILS) display; the schedule was found to be satisfactory. Postflight comments from HiMAT pilots indicated that the handling qualities during landing approach were significantly improved as a result of the modified gain schedule.

In a separate development, a visual display that was used for engineering purposes was implemented into the simulator during the latter portion of the flight test program when simulation was no longer required to support the remaining flights. While the addition of a visual display is known to significantly improve the fidelity of a simulation system, the need for such a system in RPRV simulation at Ames Dryden was felt to be reduced since pilots had an opportunity to conduct proficiency flights with an RPRV Piper Comanche PA-30 aircraft. Nevertheless, when a visual display became available in the simulation laboratory, a decision was made to determine the effectiveness of this type of visual display in the simulation of visual RPRV flight. The RPRV evaluation described in this paper was designed to focus on the utility of a visual display of this type while studying the influence of changes in lateral-stick gearing gains of remotely piloted research vehicle handling qualities during simulated approaches and landings. This study was undertaken to compare evaluations of pilots using a simulated visual display of the runway scene and a simulated ILS display with the results of actual flight tests, using the HiMAT aircraft as a representative remotely piloted research vehicle.

What this says is:

1. "The vehicle was flown with cockpit display instruments until the landing approach phase of the flight when the camera aboard the aircraft was activated to provide the pilot with a television display during the approach."
2. During the operational phase of the HiMAT program, a simulator was used to adjust the control laws for the primary control system. The display presented to the pilot of this simulated system was a display of an instrument landing system (ILS).
3. Separately, a study was undertaken to compare evaluations of pilots using a simulated visual display of the runway scene and a simulated ILS display with the results of actual flight tests, using the HiMAT aircraft as a representative remotely piloted research vehicle.

There is no mention of a terrain database or any suggestion that the simulated visual display of the runway scene was ever used to control a real aircraft. It was never anything other than a simulation.

Sarrafian does not show a picture of the ILS display. He probably assumed that anyone reading the report in 1984 would know what one looks like.

The following is a modern picture and an explanation of an ILS display from NASA [\[Ref. 12\]](#). Note that the sky above the horizon line is blue; the ground below the horizon line is brown. There is no depiction of terrain. This looks a great deal like what is now known as a Primary Flight Display.




Instrument Landing System (ILS)

An aircraft on an instrument landing approach has a cockpit with computerized instrument landing equipment that receives and interprets signals being from strategically placed stations on the ground near the runway. This system includes a "Localizer" beam that uses the VOR indicator with only one radial aligned with the runway. The Localizer beam's width is from 3° to 6°. It also uses a second beam called a "glide slope" beam that gives vertical information to the pilot. The glide slope is usually 3° wide with a height of 1.4°. A horizontal needle on the VOR/ILS head indicates the aircraft's vertical position. Three marker beacons (outer, middle and inner) are located in front of the landing runway and indicate their distances from the runway threshold. The Outer Marker (OM) is 4 to 7 miles from the runway. The Middle Marker (MM) is located about 3,000 feet from the landing threshold, and the Inner Marker (IM) is located between the middle marker and the runway threshold where the landing aircraft would be 100 feet above the runway.

The VOR indicator for an ILS system uses a horizontal needle in addition to the vertical needle. When the appropriate ILS frequency is entered into the navigation radio, the horizontal needle indicates where the aircraft is in relation to the glide slope. If the needle is above the center mark on the dial, the aircraft is below the glide slope. If the needle is below the center mark on the dial, the aircraft is above the glide slope.

The following is a picture of the image Sarrafian produced in his simulator (*Figure 9 - Simulated landing approach conditions on glideslope*):



The display was created with an Evans and Sutherland Picture System [\[Ref. 16\]](#) using a calligraphic monitor. The term **calligraphic** means that the system only drew lines and dots. This type of system is also called **Random Scan** because the electron beam in the CRT can be moved anywhere on the screen, as opposed to a Raster Scan system, which draws a raster. Atari's term for **Random Scan** was **XY** or **Vector** and was used in several games in the late 1970s and early 1980s such as Asteroids, BattleZone, and Star Wars.

The solid areas are filled-in by drawing lots of lines.

The lines above the horizon are presumably meant to indicate the sky. The grid lines are presumably meant to indicate the ground. There is no suggestion that the grid lines are produced from a digital elevation database. There would be no reason to use a digital elevation database because the system was used only to simulate landings. (Indeed, the name of the study is "Simulator Evaluation of a Remotely Piloted Vehicle Lateral Landing Task Using a Visual Display.")

Another HiMAT report is **THE ROLE OF SIMULATION IN THE DEVELOPMENT AND FLIGHT TEST OF THE HIMAT VEHICLE** by M. B. Evans and L. J. Schilling [\[Ref. 13\]](#).

From Evans and Schilling:

Visual Landing Aid

Actual. - Cues to the pilot during landing included the cockpit instruments, ILS/glideslope error indicators, television transmission from the vehicle, calls on the radio from the chase pilot, and space-positioning calls from the flight-test engineer.

Simulation model. - For most of the program, the landing cues for the pilot in a HiMAT simulation included only the instruments, mapboards, and the ILS/glideslope error indicators. Although these are all valid cues, they could not achieve the same effect as the television transmission used in actual flight. During flight, as soon as the pilot can identify the runway, his scan focuses more on the television picture and less on the cockpit instruments. To help alleviate this lack of fidelity in the simulation, a display of the runways on the dry lakebed was developed on a recently purchased Evans and Sutherland Graphics System.

HiMAT was actually flown using cockpit instruments, ILS/glideslope error indicators, television transmission from the vehicle, calls on the radio from the chase pilot, and space-positioning calls from the flight-test engineer.

It was not flown using synthetic vision.

The AUVSI Authors have reproduced a picture in their article with the caption, "The HiMAT RPV remote cockpit showing synthetic vision display. Photo courtesy of NASA."

This picture is identical to the picture in Sarrafian Figure 5 [\[Ref. 11\]](#), August 1984, PDF page 10} but the Sarrafian picture has a different caption. It says, "HiMAT simulation cockpit."



The HiMAT RPV remote cockpit showing synthetic vision display. Photo courtesy of NASA.



Fig. 5 HiMAT simulation cockpit.

ECN 22757

The monitor shows a picture of the kind shown in Sarrafian Figure 8 or Figure 9 (along with a considerable amount of what appears to be reflected glare). The picture was produced by an Evans and Sutherland Picture System which requires a calligraphic monitor.

Here's the thing. "The vehicle was flown with cockpit display instruments until the landing approach phase of the flight when the camera aboard the aircraft was activated to provide the pilot with a television display during the approach."

In order to display the video from the camera aboard the aircraft, the Ground Cockpit that controlled the aircraft had to have a raster-scan monitor.

Raster-scan monitors and Calligraphic monitors are incompatible.

The picture shows the Simulation Cockpit, and the Simulation Cockpit could not be used to control the aircraft.

Why did the AUVSI Authors change the caption?

Visual-Proprioceptive Cue Conflicts in the Control of Remotely Piloted Vehicles, Reed, 1977

In paragraph 9 the AUVSI Authors state:

Also in 1979, the Air Force published research identifying human factors problems that would have to be overcome in RPV cockpit design ("Visual- Proprioceptive Cue Conflicts in the Control of Remotely Piloted Vehicles" by Reed in 1977). NASA would use this in the design of the HiMAT RPV 3D visual system in 1984.

[Ref. 14](#) provides the link to the Reed report.

This is what the Reed report was about:

1. From page 5 (PDF page 8):


An operator is asked to maneuver a remotely piloted vehicle (RPV) from an airborne control station (a mother ship). This station is equipped with a television monitor, control stick, and other controls and displays necessary to maneuver the RPV through a specified course. The RPV, containing a television camera mounted in its nose, relays an image of the terrain to be displayed on the television monitor in the control station. Thus, the visual scene displayed to the operator represents the scene viewed by the camera. The task of the operator is to use the controls and displays to "fly" the RPV in much the same way he would fly a conventional aircraft.

The scenario is complicated by several factors. First, the visual inputs to the operator from the RPV are independent of the motion inputs from the control station. Thus, the operator will experience motion cues that are uncorrelated with the visual inputs received from the RPV. Second, while traditional pilot training programs operate on the philosophy that proprioceptive cues provided by the motion of the aircraft should be disregarded, research has shown that these cues are compelling, not easily ignored, and may improve performance when used in training simulators (see, for example, Borlace, 1967; Cohen, 1970; Douvillier, Turner, McLean, & Heinle, 1960; Fedderson, 1961; Huddleston & Rolfe, 1971; Rathert, Creer, & Douvillier, 1959; Ruocco, Vitale, & Benfari, 1965). The task simulated in the experiment presented here, however, required that the RPV operator disregard sensations of motion in order to maintain adequate performance. Under conditions of visual -proprioceptive conflict (as when the mother ship and/or the RPV are in turbulence) the stereotypic responses of pilots to correct angular accelerations will be inappropriate.

2. From page 7 (PDF page 10):

Visual system. The visual system consisted of a three-dimensional terrain model (a modified SMK-23 Visual Simulator, The Singer Company), television camera and optical probe, and three monochromatic television monitors. The terrain model provided "real-world ground cues for visual tracking over the surface. The real-world to terrain model scale was 3,000:1 and represented a six by twelve-mile (9.65 by 19.3 km) area. The model was mounted on an endless belt that was servo-driven to represent the continuous changes in scene as the simulated RPV traveled along north-south directions. A television camera viewed the terrain model through an optical probe that contained a servoed mechanical assembly to permit the introductions of heading, roll, and pitch. Both the camera and probe were mounted on a servo-driven carriage system that moved across the terrain model to simulate movement of the RPV along east-west directions and in and out to simulate altitude changes.

The SMK-23 was also used in The Lunar Roving Vehicle (LRV) simulator [\[Ref. 15\]](#). This shows what an SMK-23 looks like.



The SMK-23 used a television camera with an optical probe to fly over the terrain model contained on a servo-driven endless belt.

If Reed had had *synthetic vision* why would he have used the SMK-23 mechanical contraption?

The only link between Reed and HiMAT is that the HiMAT aircraft could be landed by either a ground-based pilot or an airborne controller (the backseat chase pilot in the TF-104G aircraft). [\[Ref 13 – Evans & Schilling, PDF page 9\]](#)

Actual.- The backup control system (BCS) is the second of the two independent flight control systems required for the Hi MAT program. The BCS control law is resident in one of the two onboard digital computers. The BCS is a full-authority, three-axis, multirate digital controller with stability augmentation functions and mode command functions (ref. 4). Each of seven modes is semiautomatic with the pilot providing direction by way of discrete command inputs. The BCS commands elevons for pitch and roll control and rudders for yaw control, and has an autothrottle for speed modulation.

The BCS was designed to provide well-controlled dynamics throughout the flight envelope, to have the ability to recover from extreme attitudes, and to bring the vehicle to a selected site and effect a successful landing by either a ground-based pilot or an airborne controller (the backseat chase pilot in the TF-104G aircraft). It was designed to provide these features for an unstable vehicle configuration of no more than 10-percent aft mean aerodynamic chord center-of-gravity location. The original HiMAT BCS was developed by Teledyne Ryan Aeronautical for the onboard microprocessor computer, and was programmed entirely in Intel 8080 assembly language.

While HiMAT might have used the results of the Reed report to select the airborne controller (the backseat chase pilot in the TF-104G aircraft) Reed did not use synthetic vision and neither did HiMAT.

Simulators

The AUVSI Authors describe several flight simulators, such as the RC AeroChopper by Ambrosia Microcomputer Products [Paragraphs 15 and 16] and Bruce Artwick's "Flight Simulator" for the Apple II, which ultimately became Microsoft Flight Simulator. [Paragraph 5]

RC AeroChopper was developed by David R. Stern at Ambrosia Microcomputer Products. The following is from an email correspondence with Mr. Stern:

Question 1: Did AeroChopper use a 3D terrain database?

Mr. Stern: I guess it did, although the ground was a plane with 3D objects (and a 2D runway) scattered around (trees, pylon, towers with crossbar to fly under).

Question 2: If so, did it represent real terrestrial terrain?

Mr. Stern: No.

Question 3: Did AeroChopper do real 3D?

Mr. Stern: Yes. All the objects including the aircraft were described by a list of points, a list of point pairs for lines and a list of which points were in each polygon, each point had an x,y and z component. The original version was started in 1984, shown at the first R/C show (I think in Storm Lake Iowa) in the summer of 1986, had only vector graphics. About 1990 I changed to filled polygons. The aircraft was rotated (pitch, yaw and roll) slightly each frame with respect to the fixed coordinate system. Then the aircraft and all background objects were rotated and scaled depending on the relative position of the "camera".

The view on the screen was initially from a fixed point about eye level for a standing R/C pilot. The "camera" rotated to keep the aircraft on the screen. In the late 80s, I added two different viewpoint options ("camera" flying near the aircraft) . One mode was just behind the aircraft, looking in the direction the aircraft was pointed. The second camera mode followed the aircraft to keep it from getting too far away but slowed and stopped as the aircraft got closer. You can often see the ground objects from the air in these modes.

I developed the first version on the Atari 520 ST computer in 68000 assembly language. Then I developed an Amiga version and then a Macintosh version. In about 1991, I developed an 80286 version for a DOS machine. (The latest version requires a Windows 98 or older machine with an RS232 port and runs under DOS)

RC AeroChopper was a significant achievement for the home computers available at the time and was a highly regarded simulator {[Ref. 17](#)} but:

1. It did not use a digital elevation database; "... the ground was a plane with 3D objects (and a 2D runway) scattered around (trees, pylon, towers with crossbar to fly under)," and thus, did not represent real terrestrial terrain.

2. It did not provide a computer-generated image of the external scene topography from the perspective of the flight deck that is derived from aircraft attitude, high-precision navigation solution, and database of terrain, obstacles and relevant cultural features.

It was not synthetic vision. It was a simulator.

Now, let's discuss Microsoft Flight Simulator [{Ref. 18}](#):

Flight Simulator 5.1 was released in 1995. Microsoft Flight Simulator did not start using 3D terrain until Flight Simulator 2000 Pro, released in late 1999.

From [Ref. 19](#):

GRAPHICS

We now have another complete globe to fly around. With the new mesh style scenery we have real elevation points that make the surrounding terrain rise and fall like the real earth. We have no more flat areas that just pop up into place at the last minute during a landing approach!

Even then, it is not clear if the terrain database represents real terrain or is made up.

The article mentions the new GPS feature:

737 Panel

The 737-400 panel is very nicely done. Simple, yet effective. This is where FS2000 is not much different than FS98. However, the overall clarity, coloring, detailing and some new systems make it much better. We now have nice popups for the throttle quadrant, radio stack, compass and best of all the new GPS.

The GPS is part of the simulated 737 control panel. There is no suggestion that a physical GPS unit can be connected to the program.

A simulator is not synthetic vision. A simulator might do a good job simulating synthetic vision. It might even use a Digital Terrain Elevation Database representing real terrestrial terrain, but that does not make it synthetic vision. It is a simulator. If it does not control a physical aircraft it is not synthetic vision.

When Did NASA Start Working on Synthetic Vision?

From [Ref 20](#):

NEWS RELEASE

May 28, 1999

Synthetic Vision Could Help General Aviation Pilots Steer Clear of Fatalities

Hampton, Virginia -- Research Triangle Institute and six companies are teaming up to develop revolutionary new general aviation cockpit displays to give pilots clear views of their surroundings in bad weather and darkness.

The RTI Team includes Flight International, Inc., Newport News, Virginia. (a GA aircraft user) and Archangel Systems, Inc., Auburn, Alabama, who are committed to early commercialization and will make significant cost share contributions. The starting point for the new system is Archangel's TSO'd and STC'd Cockpit Display System.

RTI also has teamed with Seagull Technology, Inc., Los Gatos, California (a GPS and attitude/heading reference system technology firm), Crew Systems, Inc., San Marcos, Texas, (a designer of low-cost head up displays), and Dubbs & Severino, Inc., Irvine, California (an award-winning terrain database design company). In addition, FLIR Systems, Inc., Portland, Oregon (an infrared instrument manufacturer) has agreed to evaluate the costs and benefits of existing weather penetrating sensor technology.

Limited visibility is the greatest factor in most fatal aircraft accidents, according to the Aviation Safety Program at NASA's Langley Research Center in Hampton, VA. The RTI team is among six selected by NASA to develop different applications of Synthetic Vision.

The RTI team will design, develop, and certify a Synthetic Vision system for general aviation aircraft. The purpose is to reduce or eliminate controlled flight into terrain caused by visibility-induced human error.

Synthetic Vision is a display system that will offer pilots an electronic picture of what's outside their windows, no matter the weather or time of day. The system combines Global Positioning Satellite signals with terrain databases and graphical displays to draw three-dimensional moving scenes that will show pilots exactly what's outside.

The NASA Aviation Safety Program envisions a system that incorporates multiple sources of data into cockpit displays. The displays would show hazardous terrain, air traffic, landing and approach patterns, runway surfaces and other obstacles that could affect an aircraft's flight.

The NASA Aviation Safety Program is a partnership with the FAA, aircraft manufacturers, airlines and the Department of Defense. This partnership supports the national goal announced by President Clinton to reduce the fatal aircraft accident rate by 80 percent in 10 years and by 90 percent over 25 years.

Research Triangle Institute is an independent, not-for-profit organization that conducts R&D and provides technical services to industry and government. With a staff of more than 1,600 people, RTI is active in aerospace and many other fields of applied technology. RTI was created in 1958 as the centerpiece of North Carolina's Research Triangle Park, where its headquarters are located. RTI's Aerospace Technology Center in Hampton, Virginia, will carry out the Synthetic Vision project.

In a separate press release dated May 13, 1999 NASA announced {from [Ref. 21](#)}:

Industry teams submitted 27 proposals in four categories: commercial transports and business jets, general aviation aircraft, database development and enabling technologies. NASA and researchers from the Federal Aviation Administration and Department of Defense evaluated the proposals' technical merit, cost and feasibility.

NASA has committed \$5.2 million that will be matched by \$5.5 million in industry funds to advance Synthetic Vision projects over the next 18 months. More money is expected to be designated later to accelerate commercialization and make some systems available within four to six years.

Among the team leaders selected for the first phase of the program are: Rockwell Collins, Inc., Cedar Rapids, IA; AvroTec, Inc., Portland, OR; Research Triangle Institute, Research Triangle Park, NC; Jeppesen-Sanderson, Inc., Englewood, CO; the Avionics Engineering Center of Ohio University, Athens, OH; and Rannoch Corporation, Alexandria, VA.

Rockwell Collins, Inc. will receive funds to develop synthetic vision for airliners and business jets. The AvroTec, Inc. and Research Triangle Institute groups will use their awards to create technologies for a general-aviation synthetic vision system. A team led by Jeppesen-Sanderson, Inc. will receive funds to develop terrain database requirements and system approaches. The Avionics Engineering Center of Ohio University and Rannoch Corporation will use their awards to design specific component technologies for Synthetic Vision.

When did NASA start working on Synthetic Vision?

The answer is: 1999.

When did NASA first use synthetic vision to control a UAV?

It was in the X-38 project.

From [Ref 22](#): "Virtual Cockpit Window" for a Windowless Aerospacecraft

Wednesday, January 01 2003

A software system processes navigational and sensory information in real time to generate a three-dimensional-appearing image of the external environment for viewing by crewmembers of a windowless aerospacecraft. The design of the particular aerospacecraft (the X-38) is such

that the addition of a real transparent cockpit window to the airframe would have resulted in unacceptably large increases in weight and cost.

When exerting manual control, an aircrew needs to see terrain, obstructions, and other features around the aircraft in order to land safely. The X-38 is capable of automated landing, but even when this capability is utilized, the crew still needs to view the external environment: From the very beginning of the United States space program, crews have expressed profound dislike for windowless vehicles. The well-being of an aircrew is considerably promoted by a three-dimensional view of terrain and obstructions. The present software system was developed to satisfy the need for such a view. In conjunction with a computer and display equipment that weigh less than would a real transparent window, this software system thus provides a "virtual cockpit window."

The key problem in the development of this software system was to create a realistic three-dimensional perspective view that is updated in real time. The problem was solved by building upon a pre-existing commercial program — LandForm C3 — that combines the speed of flight-simulator software with the power of geographic-information-system software to generate real-time, three-dimensional-appearing displays of terrain and other features of flight environments. In the development of the present software, the pre-existing program was modified to enable it to utilize real-time information on the position and attitude of the aerospacecraft to generate a view of the external world as it would appear to a person looking out through a window in the aerospacecraft. The development included innovations in realistic horizon-limit modeling, three-dimensional stereographic display, and interfaces for utilization of data from inertial-navigation devices, Global Positioning System receivers, and laser rangefinders. Map and satellite imagery from the National Imagery and Mapping Agency can also be incorporated into displays.

The Press Release from Rapid Imaging Software, Inc., which did the synthetic vision work for the X-38, states [{Ref. 23}](#)



On December 13th, 2001, Astronaut Ken Ham successfully flew the X-38 from a remote cockpit using LandForm VisualFlight as his primary situation awareness display in a flight test at Edwards Air Force Base, California. This simulates conditions of a real flight for the windowless spacecraft, which will eventually become NASA's Crew Return Vehicle for the ISS. We believe that this is the first test of a hybrid synthetic vision system which combines nose camera video with a LandForm synthetic vision display. Described by astronauts as "the best seat in the house", the system will ultimately make space travel safer by providing situation awareness during the landing phase of flight.

Other References cited by the AUVSI Authors

"Pathway-in-the-Sky Contact Analog Piloting Display," Knox and Leavitt, 1977

In the article the AUVSI Authors state in Paragraph 7:

In 1977, NASA researcher Charles Knox published "Pathway-in-the-Sky Contact Analog Piloting Display," which included a complete design for a synthetic vision system. It featured a computer that projected a 3D view of the terrain given an aircraft's position and orientation. This out-the-window perspective view was displayed on a CRT type display. Such displays were called "Pictorial Format" avionics systems, but we recognize them as containing all of the essential elements of a modern synthetic vision display.

The pictures that will be reproduced shortly are from the Knox report (Charles E. Knox and John Leavitt). I have placed them with the descriptions from Knox pages 3-4. The complete Knox report is [Ref. 24](#).

Everything comes together in Knox Figure 4, which shows the Airplane track-angle pointer and scale, the Airplane symbol with shadow superimposed, the Flight-path-angle scale, the Flight-path prediction vector, the Earth horizon, the Roll pointer, the Airplane altitude deviation from path, the Airplane flight-angle bars, the Programmed path-angle indicator, the Potential flight-path-angle box, and the Programmed flight path.

The Programmed flight-path consists of two three-dimensional lines showing the predicted flight path of the airplane. Knox and Leavitt's work is significant but there is no terrain, there is no digital elevation database. There is no synthetic vision.

From Knox **Description of Path-in-the-Sky Contact Analog Piloting Display** [{Ref. 24}](#):

Display Symbolology

The format of the PITS contact analog display shows airplane attitude information in the form of bank angle and pitch changes. Airplane performance information is shown in the form of airplane flight-path angle and flight-path acceleration (which may be used as thrust- or energy-management control). Both vertical and lateral path deviations during a tracking task are shown in pictorial form.

Path-tracking situation information is shown through a combination of an airplane symbol, a vertical projection of the airplane symbol with an extended center line drawn at the altitude of the path, a flight-path predictor, and a drawing of the programmed path (fig. 1). These four pieces of symbology are drawn in a perspective display format as if the observer's eye were located behind and above the airplane.

The airplane symbol is a tetrahedron with a smaller tetrahedron at the tail to visually enhance pitch changes. The airplane's true position with respect to the path is at the symbol's apex. The symbol rolls and pitches about its apex in accord with the real airplane's attitude.






Figure 1.- Path, shadow, flight-path predictor, and airplane symbology.

Altitude deviations from the programmed path are indicated to the pilot pictorially by a vertical projection of the airplane symbol. The projection, drawn with dashed lines, may be thought of as a shadow; as shown in figure 2, it remains directly above or below the airplane at the altitude of the path. If the airplane is above the programmed path, the shadow appears to be below the airplane symbol. If the airplane is below the programmed path, the shadow appears to be above the airplane symbol.



(a) Above path.



(b) Below path.

Figure 2.- Airplane symbol and shadow interactions during altitude deviations.

Since the shadow is always drawn directly above or below the airplane symbol, the pilot may readily identify lateral tracking deviations when they are combined with a vertical tracking error. Figure 3 shows the perspective view of the shadow, the airplane symbol, and the path when the airplane is above and to the left of the path.




Figure 3.- Airplane above and to left of path.

Altitude deviations from the programmed path are also shown to the pilot in numerical form in a box in the upper right-hand corner of the display (fig. 4). The pilot is expected to use this information when the path and shadow are out of the display field of view, such as could occur during initial path captures.

A flight-path prediction vector (fig. 4) in the horizontal plane is attached to the shadow. The prediction vector, indicated by a dashed line, shows the airplane's predicted path for the next 10 sec based on the airplane's present bank angle and ground speed. An extended shadow center line drawn from the apex of the shadow in the direction of the present track angle, is also shown to aid the pilot with the lateral tracking task.




Figure 4.- The PITS contact analog display symbology.

Figure 5 shows the flight-path prediction vector and the present track indicator with the airplane in a left bank of 13° .




Figure 5.- The PITS display concept showing airplane below path and climbing in a left bank of 13° .

“The Electronic Terrain Map: A New Avionics Integrator”, Small, D.M., 1981

In the article the AUVSI Authors state in Paragraph 8:

In 1979, the U.S. Air Force completed its "Airborne Electronic Terrain Map Applications Study" and in 1981 published "The Electronic Terrain Map: A New Avionics Integrator" describing how a computerized terrain database could be displayed as an out-the-window 3D view allowing the pilot to "see" even at night and in other limited visibility situations.

No, Small did not describe “how a computerized terrain database could be displayed as an out-the-window 3D view allowing the pilot to ‘see’ even at night and in other limited visibility situations.”

The Small report discusses the concept of a digital Electronic Terrain Map (ETM) and proposes that it be used for:

1. Navigation;
2. Terrain Following/Terrain Avoidance (TF/TA);
3. Threat avoidance, analysis, warning, and display;
4. Terrain Masking;
5. Weapon delivery;
6. Route planning.

He does say, “An electronic map subsystem can generate perspective scenes, which are essentially computer generated images of the surrounding area, and an electronic map should be much easier to interpret,” but:

1. The statement must be understood according to the meaning it would have had at the time the article was written (circa 1981); and
2. Wishing for a desired result is not the same as teaching how to do it.

This is what the Small report [{Ref. 25}](#) is about:

From the section INTRODUCTION:

INTRODUCTION

Currently, the Air Force has in the inventory paper and film map systems, which were developed to support the high and level flight environment. These maps were an effective means of tapping the vast files of information stored in the Defense Mapping Agency (DMA) data base, when the crew had time to study and interpret them (in fact, much of their value was actually obtained from pre-flight mission preparations). Interviews with pilots indicate that paper maps are less useful for low altitude flights. Film maps with CRT annotation are somewhat better, but still have a fundamental limitation in that it takes an operator to access any information. That is, it is not possible to transfer information directly from the data base to any other avionics system when it is stored on paper or film maps in what is essentially an analog form.

The map reading process is a demanding task that can be simplified by using a digital map subsystem which accesses the information needed and presents it in a form which can be easily interpreted. At low altitude, and with a line of sight limited to the next ridge line, it's very difficult to interpret standard paper maps, which are presented as a vertical projection of a large

area. An electronic map subsystem can generate perspective scenes, which are essentially computer generated images of the surrounding area, and an electronic map should be much easier to interpret. In addition, essential information from the map data base can be placed on the pilots Head Up Display, reducing the need for head down operations.

Paper maps are clumsy to use, whether you are flying an aircraft or driving a car. An electronic map, if properly done, would make using a map easier.

However, whether the map is electronic or on paper, you still have to know where you are. Small has not addressed that issue in this section.

The issue of what Small might mean by "perspective scenes" will be addressed later.

From the section FUTURE AIRCRAFT SYSTEM:

FUTURE AIRCRAFT SYSTEM

The purpose of adding an ETM subsystem to a future avionics suite is to provide map data and displays that can be interfaced with other subsystems to improve the performance of the terrain following/terrain avoidance (TF/TA), threat avoidance and navigation avionics subsystems. The requirement for the simultaneous exchange of processed map data by three or four avionics subsystems will be the most difficult objective and important feature of the ETM. Development and incorporation of the advanced ETM concepts and technologies will be required to augment future threat avoidance, navigation, TF/TA, and weapon delivery avionics subsystems. Applications/examples of using these ETM concepts and/or technologies and the utilization of an ETM subsystem as a source of information follows.

TF/TA

The first example will be the automatic TF/TA avionics subsystem. Our existing automatic TF subsystems operate using only active sensors as sources of terrain profile information (i.e. radar). This makes the subsystem totally dependent on the limitations of this single information source. In case of radar, range is limited to line of sight. Absolutely no information is available beyond line of sight. This forces the TF subsystem to provide unnecessarily large clearances over ridges to avoid the following peak which may or may not be imminent. Further, the TF subsystem must radiate on an almost continuous basis to provide a continuous terrain profile. Consequently detection and jamming are TF subsystem vulnerabilities. A digital terrain map could provide a second source of information to the TF flight command processing subsystem and the use of the map could serve as a backup in case of radar failures or jamming. The ETM could provide information concerning beyond line of sight conditions, enlarge the total field of view scanned for turning, and avoid the reduction of the duty cycle of the radar emission. In fact, this ability to scan the terrain to the side without turning and looking beyond the line of sight makes it possible for the first time to consider true automation of the TA function. Because of limitations in the existing DMA data base, the approach should be cautious and an active sensor will be needed to make absolute clearance measurements. None the less, the application of stored data, to the TF/TA problem can potentially have tremendous impact on Air Force capabilities in the low altitude flight mission.

1. Existing Terrain Following systems use active radar to profile the terrain. The radar is line-of-sight, so it cannot see farther terrain hidden by closer terrain.
2. An Electronic Terrain Map would allow you to determine what is over the next ridge. However, “Because of limitations in the existing DMA data base, the approach should be cautious and an active sensor will be needed to make absolute clearance measurements.

You still need to know where you are so you can locate your position on the map.

THREAT AVOIDANCE

The second example will be the threat avoidance avionics subsystem. The whole purpose of low altitude missions is to reduce the probability of detection and attrition. If the threat avoidance problem is solved without regard to the location and lethal range of threats, the resultant path may place the aircraft in greater jeopardy than before. Terrain masking and launch dynamics limitations must be exploited to the fullest. Careful selection of the aircraft’s routes to the target may be done by the crew or automatically. In either case, a digital map is required to provide the terrain information and the position of the threats identified by the avionics system. Pre-mission planning can provide a starting point for this analysis, but the dynamics of the threat assessment makes it essential that the crew be able to redefine the mission as new information is received from command and control functions or via the aircraft’s own suite of threat defense sensors.

1. If you have a good terrain map you can use the terrain to hide your aircraft from those whom you do not want to know where you are or if you are even in the area.
2. If your terrain map shows you where the threats are, don’t go there.

You still have to know your map position.

NAVIGATION

The third example will be the navigation avionics subsystem. With the addition of a correlator to the avionic suite and using the on-board sensors together with the ETM, navigation can be accomplished. Also, by displaying the ridge lines derived from stored terrain data on the head up display, passive navigation is possible. Hence, the ETM could also improve the utilization of the navigation subsystem.

Small does not say what he means by a “correlator” or which onboard sensors he would use them with.

There can be several types of “correlators.”

1. You can visually look out your aircraft window at the terrain (mountains, lakes, rivers) and cultural features (towers, highways) and then look at a map and try to find them. Then you figure out where you would be on the map to see what you are seeing. The map can be paper or electronic. An example of a paper map converted to digital format is in [Ref 26](#). This is part of the Washington Sectional Aeronautical Chart, Scale 1:500,000 55th Edition, published March 3, 1994 by U.S. Department of Commerce National Oceanic and Atmospheric Administration National Ocean Service. [Click Here for map PDF](#). If

you are not familiar with the symbology used in paper sectional maps here is the [Washington Legend](#).

If you use the Zoom and Pan features of Acrobat you will see the advantages of an electronic version of a paper map (i.e., a digital map).

2. You can use a computer to do the correlation, such as the method taught by Horn and Bachman in **Using Synthetic Images to Register Real Images with Surface Models**. [\[Ref. 27\]](#)

Abstract: A number of image analysis tasks can benefit from registration of the image with a model of the surface being imaged. Automatic navigation using visible light or radar images requires exact alignment of such images with digital terrain models. In addition, automatic classification of terrain, using satellite imagery, requires such alignment to deal correctly with the effects of varying sun angle and surface slope. Even inspection techniques for certain industrial parts may be improved by this means.

Small has not mentioned *Terrain Referenced Navigation*. In Terrain Referenced Navigation a Radar or Lidar is used to take a few elevation measurements of the terrain. These measurements are matched to the terrain in a digital terrain elevation database.

An early example of Terrain Referenced Navigation is U.S. Patent 3,328,795 **Fixtaking Means and Method** issued June 27, 1967 to Hallmark. [\[Ref 28\]](#) From Column 2, lines 18-53:

Previously proposed fixtaking and navigational systems have sought to utilize terrain elevation data, and they have been based upon the analog comparison of sample data which are the continuous, analog representation of continuous variations in terrain elevations, with similar data contained in contour maps employed as such. At least some of the sample and known data hence have always been graphically or photographically displayed on actual sheets of paper, rectangles of photographic film, etc., and the values represented thereby have been shown as physically measurable along at least two axes. Because of the nature of the data employed, cumbersome and unwieldy equipments for photographic development, superposition of map over map, orthogonal adjustments of one set of data relative to another, etc. have been unavoidable sources of added weight, complexity, error, and malfunction.

The present invention does not employ continuously recorded, analog data, but has as one of its bases the use of quantized terrain altitude information taken at discrete points. A numerical comparison of sample and prerecorded data is performed at high speed, and with results predictable and repeatable for the same inputs, by a digital computer. Since the digital computer and associated components are relatively unaffected by noise, vibrations, nuclear radiation, etc., no equipment is required for performing two-dimensional data comparisons, and no feedback or nulling circuitry is needed for determining the point of best physical correlation of the sample with the pre-recorded data. As distinguished from systems utilizing analog information, the digital computer is free from the sources of error unavoidably present where analog comparisons are made and hence is not only more accurate but is able to tolerate relatively large errors in sample and known data values without compromising fixtaking accuracy.

TERCOM (Terrain Contour Matching) uses contour matching instead of elevations. **U.S. Patent 4,347,511 Precision navigation apparatus** issued August 31, 1982 to **Hofmann , et al.** [\[Ref. 29\]](#) mentions:

"Aviation Week & Space Technology", Feb. 25, 1974, page 50, ff, discloses the *Tercom* process. In the latter, barometric measuring devices and radio altimeters produce altitude profiles during specific time intervals of a flight over characteristic terrain. The one-dimensional differential profile between the barometric altitude and altitude above ground is compared with a two-dimensional reference profile. Here, the measured altitude profile is adjusted until the best correlation is achieved, so that the exact position of the aircraft results.

There are some problems with Terrain Referenced Navigation and Tercom:

1. They are not reliable if the terrain changes after the Digital Terrain Map is made. Terrain can change seasonally due to snow accumulations or permanently due to vegetation growth (trees) or new buildings (technically, a cultural feature).
2. They do not work over large flat terrain. [{See Ref. 30}](#)
3. They do not work over bodies of water.

Although Terrain Referenced Navigation and Tercom systems that use Radar or Lidar still send out signals that can be detected, the signals are far less detectable than the signals used in Small's description of TF/TA systems. Small's TF/TA system uses a radar to scan the terrain, which is why it cannot see beyond the next ridge.

Small's omission of Terrain Referenced Navigation and Tercom is puzzling.

Small gives a choice between Radar-scanned terrain and finding your location on a map using an undefined method of adding a correlator to the avionics suite and using the on-board sensors together with the Electronic Terrain Map (ETM).

What did Small mean when he said, "An electronic map subsystem can generate perspective scenes, which are essentially computer generated images of the surrounding area, and an electronic map should be much easier to interpret?"

In the 1980s (and well into the 1990s) the conventional wisdom was that Real 3D graphics was too computationally intensive to do in real time without large and very expensive hardware.

Honeywell was the leader in avionics. Harris was probably a close second. They both spent the 1980s and 1990s competing with each other to see who could do the best fake 3D.

For example, U.S. Patent 4,660,157 **Real time video perspective digital map display method** issued April 21, 1987 to Beckwith, et al. [{Ref. 31}](#)

Instead of mathematically rotating the points from the database the '157 Patent accounts for the aircraft's heading by controlling the way the data is read out from the scene memory. Different heading angles result in the data being read from a different sequence of addresses.

From Column 3, lines 21 - 38:

The addresses of the elevation data read out of the scene memory representing points in the two-dimensional scene of the terrain are then transformed to relocate the points to positions where they would appear in a perspective scene of the terrain. Thus, each point in the two-dimensional

scene is transformed to its new location in the perspective scene to be displayed on the viewing screen, and in the process, the data is automatically oriented with a heading-up disposition. The transformed points are then stored in a speed buffer for further processing by sun angle and line writing logic prior to being stored in a display memory from which data is read out to the display screen. Since data in the display memory represents one-to-one data to be displayed on the CRT, this data will be referred to as pixels (picture elements) in terms of its storage in the display memory for transfer to the CRT display.

The '157 patent accounts for the roll attitude of the aircraft by mathematically rotating the screen data after it is projected. From Column 12, lines 42 - 47:

The points which are output by the perspective transform circuit 110 are supplied to a screen rotation circuit 120 which serves to rotate the display data in accordance with the roll of the aircraft so that the display will accurately depict the view as it would appear, if visible, through the window of the aircraft.

Beckwith displays only points.

Fake 3D + Only Points does not qualify as what is now considered synthetic vision.

There is Honeywell's U.S. Patent 5,179,638 **Method and apparatus for generating a texture mapped perspective view** issued January 12, 1993 to Dawson, et al. [\(Ref. 32\)](#)

It even has the word "perspective" in the title, but the perspective it produces is a trapezoidal perspective, not a real 3D projected perspective.

Dawson '638 incorporates by reference a number of other patents and patent applications, and determining exactly what Dawson meant in '638 requires following a trail through these patents. The short version is that what Dawson means by "perspective" is contained in U.S. Patent 4,884,220 **Address Generation with Variable Scan Patterns** issued November 28, 1989 to Dawson (again), [\(Ref. 33\)](#) which is incorporated by reference by Dawson '638.

After discussing the shortcomings of prior art, Dawson '220 says (Column 2, line 56 through Column 3, line 2):

This invention differs from the prior methods of perspective view generation in that a trapezoidal scan pattern is used instead of the radial scan method. The trapezoidal pattern is generated by an orthographic projection of the truncated view volume onto the cache memory (terrain data). The radial scan concept is retained, but used for an intervisibility overlay instead of the perspective view generation. The radial scan is enhanced to include a full 360 degree arc with programmable attributes. The rectangular pattern retains the parallel scan methodology for plan view map generation. Both a nearest neighbor and a full bilinear interpolation method of scan address generation are implemented.

And now we know what Dawson means by "perspective."

A real 3D perspective is a 3D projection.

Anything else is Fake 3D.

If you think Fake 3D is just as good as Real 3D then the next time someone owes you money tell them that it's ok to pay you in fake dollars.

There is also the matter that Small is only wishing for a desired result. Wishing for a desired result is not the same as teaching how to do it.

Not only did Small not teach it, he was not clear in saying what he was wishing for.

VCASS: An Approach to Visual Simulation, Kocian, D., 1977

In the article the AUVSI Authors state in Paragraph 6:

This emergence of computer flight simulation in the 1970s appears to have sparked a monumental amount of research. The U.S. Air Force began its Visually Coupled Airborne Systems Simulator (VCASS) program, with a particular eye toward future-generation fighter aircraft ("VCASS: An Approach to Visual Simulation," Kocian, D., 1977).

The Kocian report is available in [Ref. 34](#).

Summary

Kocian is about using a Helmet Mounted Display (HMD) with a Head Position Sensing System to replace large expensive hemispherical display systems used in simulators. The simulator is used to develop the visual interface used by crew members to control advanced weapon systems. This visual interface can then be used in airborne operations.

During simulation a representative visual scene is generated by the graphics or sensor imagery generators but, from Paragraph 11 (emphasis added):

For an airborne VCASS capability, it is only necessary to install the VCS components along with a small airborne general purpose computer in a suitable aircraft and interface a representative programmable symbol generator to an on-board attitude reference system in order to synthesize either airborne or ground targets.

The airborne version does not synthesize a visual scene, so it is not synthetic vision.

Details

A Visually-Coupled System is one that visually couples the operator to the other system components through the use of a Helmet Mounted Display (HMD) and Helmet Position Sensor. From Paragraph 9:

The key components of VCASS will be VCS hardware which includes the HMS and HMD. These components are used to "visually-couple" the operator to the other system components he is using. AMRL has pioneered efforts in the research, development and testing of these hardware techniques.

A system using a Helmet Mounted Display with a Helmet Position Sensor is less expensive than the hemispherical projection systems being used and produces better results. Paragraph numbers have been added to the following paragraphs from Kocian.

[1] In recent years Air Force operational units have experienced a continuing trend downward in the number of flight hours in aircraft that can be provided to each individual pilot for training and maintaining proficiency. This comes at a time when aircraft systems are becoming ever more complex and sophisticated requiring comparatively more hours for training to maintain the same relative flying proficiency. With increasing costs for fuel and aircraft and the failure of DoD funding to keep pace with these costs, the trend is almost sure to continue. In adjusting to the realities of keeping overall experience at a satisfactory level and reducing costs, procurement of aircraft simulators has become a necessity.

[2] The rapid proliferation of simulators with no standard technical criteria as a guide has resulted in the evolution of several different design approaches. Most existing visual scene simulators utilize electro-optical devices which project video imagery (generated from a sensor scan of a terrain board or a computer generated imagery capability) onto a hemispherical dome or set of large adjacent CRT displays arranged in optical mosaics with the weapon, vehicle, and threat dynamics being provided by additional computer capabilities.

[3] These large fixed-base simulators suffer from the following drawbacks. The majority of the visual projection techniques used in these simulators do not incorporate infinity optics which provide collimated visual scenes to the operator. Those which do are large and expensive and incorporate large CRT displays. The luminance levels and resolution of these displays are usually low and do not represent true ambient conditions in the real environment. Additionally, hemispherical infinity optics are difficult to implement and this technique requires excessive computer capacity to generate imagery due to the need for refreshing an entire hemisphere instantaneously, regardless of where the crew member is looking. In this regard, existing computer capability is not used effectively to match the channel capacity of the human visual system. There are also generally no stereoscopic depth cues provided for outside-of-cockpit scenes. Another important drawback to these simulators is that the visual simulation is not transferrable to the actual flight environment, i.e., the ground-based system cannot be transferred to an actual aircraft to determine simulation validity. Finally, most existing techniques are very expensive and do not allow the flexibility of incorporating other display design factors such as different head-up display image formats, fields-of-view (FOV), representative cockpit visibilities, and optional control and display interfaces.

[4] A quite different approach to solving the visual presentation problems of aircraft simulators is to employ the use of visually coupled systems (VCS). For many years it has been the mission of the Aerospace Medical Research Laboratory to optimize the visual interface of crew members to advanced weapon systems. This mission has been primarily pursued in two areas: (1) the establishment of control/display engineering criteria; and (2) the prototyping of advanced concepts for control and display interface. An important part of fulfilling this mission has been the development of VCS components which includes head position sensing systems or helmet mounted sights (HMS), eye position sensing systems (EPS) and helmet mounted displays (HMD).

During simulation a representative visual scene is generated by the graphics or sensor imagery generators. From Paragraph 7:

A more detailed analysis of the problem has produced a set of characteristics which a more ideal aircraft simulator might possess. Of primary importance is that it should be a flexible visual scene simulation providing synthesized out-of-the-cockpit visual scenes and targets, a representative vehicle whose type can be altered, threat and weapon dynamics, flexibility of control and display configurations, and inputs from sensor or real world imagery. It should be portable if possible and provide alternatives for crew station display options including number and configuration. This simulator should also be useable in both simulated air-to-ground weapon delivery and air-to-air engagement scenarios. Finally, it should be possible to use the same system in ground fixed base and motion base simulators as well as in aircraft.

However, the airborne version does not synthesize the out-the-cockpit visual scene. It only displays the symbols used in its role as a weapons controller. That is why the airborne version only needs a small airborne general purpose computer. From Paragraph 11 (emphasis added):

For an airborne VCASS capability, it is only necessary to install the VCS components along with a small airborne general purpose computer in a suitable aircraft and interface a representative programmable symbol generator to an on-board attitude reference system in order to synthesize either airborne or ground targets. This approach has the ultimate flexibility of utilizing the same symbol set, threat dynamics, etc., in the air that were originally used in the ground simulation. In either case, the crew member will engage electronic targets (either air-to-air or air-to-ground) and launch electronic weapons. His performance in these tasks in turn will be recorded and assessed for performance or utilized as training aids for the crew member or operator.

The airborne version does not synthesize a visual scene, so it is not synthetic vision as the term is now used.

In addition, the Kocian report describes a work-in-progress. From Paragraph 19:

The design considerations involved in building a helmet-mounted display for the VCASS simulation present a more formidable and subjective set of problems whose solution is not entirely clear. It is certain that a larger display field-of-view is required but how large remains an unanswered question. The optical physics that are part of the display design imposed constraints which are difficult to resolve. Currently, an interim display possessing a 60 degree instantaneous field-of-view is planned for the VCASS; however, recent studies have shown that this may not be large enough especially when viewed with one eye. This leads naturally to biocular or binocular configurations. A whole host of human factors problems then becomes important including brightness disparity, display registration, and eye dominance. The decision whether or not to include color also becomes a major design decision not only because of the engineering development required but because user acceptance may weigh heavily on this factor.

(The question whether or not to use color was later settled. The answer was color.)

U.S. Patent 5,566,073 Pilot Aid Using A Synthetic Environment
issued October 15, 1996 to Margolin

This patent was not mentioned by the AUVSI Authors.

Abstract

A pilot aid using synthetic reality consists of a way to determine the aircraft's position and attitude such as by the global positioning system (GPS), a digital data base containing three-dimensional polygon data for terrain and manmade structures, a computer, and a display. The computer uses the aircraft's position and attitude to look up the terrain and manmade structure data in the data base and by using standard computer graphics methods creates a projected three-dimensional scene on a cockpit display. This presents the pilot with a synthesized view of the world regardless of the actual visibility. A second embodiment uses a head-mounted display with a head position sensor to provide the pilot with a synthesized view of the world that responds to where he or she is looking and which is not blocked by the cockpit or other aircraft structures. A third embodiment allows the pilot to preview the route ahead or to replay previous flights.

It teaches what is now known as synthetic vision in sufficient detail that it may be practiced by a *Person having Ordinary Skill In The Art* without undue experimentation. A Person having Ordinary Skill In The Art (POSITA) is a legal term that is often fought over during patent litigation.

This patent is a continuation of Application Ser. No. 08/274,394, filed Jul. 11, 1994, which is its filing priority date. The earliest known description of the invention is in [Ref. 35](#).

For those unfamiliar with Patent Law, the Claims are the legal definition of the invention. The purpose of the Abstract is to provide search terms only.

See [Ref. 36](#) for the patent. (I am the inventor named in the patent.)

U.S. Patent 5,904,724 **Method and apparatus for remotely piloting an aircraft**
issued May 18, 1999 to Margolin

This patent was also not mentioned by the AUVSI Authors.

Abstract

A method and apparatus that allows a remote aircraft to be controlled by a remotely located pilot who is presented with a synthesized three-dimensional projected view representing the environment around the remote aircraft. According to one aspect of the invention, a remote aircraft transmits its three-dimensional position and orientation to a remote pilot station. The remote pilot station applies this information to a digital database containing a three dimensional description of the environment around the remote aircraft to present the remote pilot with a three dimensional projected view of this environment. The remote pilot reacts to this view and interacts with the pilot controls, whose signals are transmitted back to the remote aircraft. In addition, the system compensates for the communications delay between the remote aircraft and the remote pilot station by controlling the sensitivity of the pilot controls.

It teaches the use of synthetic vision (as the term is currently used) for remotely piloting an aircraft. It teaches it in sufficient detail that it may be practiced by a Person having Ordinary Skill In The Art without undue experimentation.

This patent was filed January 19, 1996, which is its priority date.

For those unfamiliar with Patent Law, the Claims are the legal definition of the invention. The purpose of the Abstract is to provide search terms only.

See [Ref. 37](#) for the patent. (I am the inventor named in the patent.)

U.S. Patent Application Publication 20080033604
System and Method For Safely Flying Unmanned Aerial Vehicles in Civilian Airspace

In the interests of full disclosure I have the following patent application pending: U.S. Patent Application Publication 20080033604 **System and Method For Safely Flying Unmanned Aerial Vehicles in Civilian Airspace.**

Abstract

A system and method for safely flying an unmanned aerial vehicle (UAV), unmanned combat aerial vehicle (UCAV), or remotely piloted vehicle (RPV) in civilian airspace uses a remotely located pilot to control the aircraft using a synthetic vision system during at least selected phases of the flight such as during take-offs and landings.

See [Ref. 38](#) for the published patent application. (I am the inventor named in the application)

The Future of Synthetic Vision

This is what the AUVSI Authors have said about synthetic vision [Paragraph 2]:

More recently it has evolved away from being a piloting aid to a potentially powerful tool for sensor operators.

and [Paragraph 22]:

The recent availability of sophisticated UAS autopilots capable of autonomous flight control has fundamentally changed the paradigm of UAS operation, potentially reducing the usefulness of synthetic vision for supporting UAS piloting tasks. At the same time, research has demonstrated and quantified a substantial improvement in the efficiency of sensor operations through the use of synthetic vision sensor fusion technology. We expect this to continue to be an important technology for UAS operation.

While I have no doubt that synthetic vision is very useful to the sensor operator, the news that its use in piloting UAVs is on its way out came as a big surprise to me.

The AUVSI Authors have an ulterior motive in making the statements. Their real objective is to make people believe synthetic vision no longer has value in controlling Remotely Piloted Vehicles (aka UAVs) and that a Remotely Piloted Vehicle that is flown using an Autonomous control system is no longer a remotely piloted vehicle and therefore a sensor operator may use synthetic vision without infringing U.S. Patent 5,904,724. See [Ref. 39](#) for the response Rapid Imaging Software's attorney sent to Optima Technology Group in 2006.

The statements made by the AUVSI Authors form a distinction without a difference unless there is a wall between the sensor operator and the pilot that results in the sensor operator having no influence on how or where the UAV is flown.

Consider the following scenarios:

1. The human sensor operator has synthetic vision; the human pilot does not. No communications is allowed between the human sensor operator and the human pilot lest the human sensor operator influence the human pilot where or how to fly the aircraft. Otherwise, it might be considered as contributing to piloting the aircraft. This results in a decidedly sub-optimal system.
2. The human sensor operator has synthetic vision; the aircraft is flown autonomously (a machine pilot). No communications is allowed between the human sensor operator and the machine pilot lest the human sensor operator influence the machine pilot where or how to fly the aircraft. Otherwise, it might be considered as contributing to piloting the aircraft. This also results in a decidedly sub-optimal system.

There are legal and political ramifications to this scenario.

Someone has to be responsible for the operation and safety of the flight. The FAA defines "Pilot in Command" as [Ref. 5](#):

Pilot in command means the person who:

- (1) Has final authority and responsibility for the operation and safety of the flight;
- (2) Has been designated as pilot in command before or during the flight; and

(3) Holds the appropriate category, class, and type rating, if appropriate, for the conduct of the flight.

It is unlikely that FAA will allow this responsibility to be delegated to a machine anytime soon. That's where the political ramifications come in. A UAV (especially a completely autonomous UAV) that injures or kills civilians would ignite a political firestorm that would ground the entire UAV fleet.

Since there must be a human in the loop to be responsible for the operation and safety of the flight, that leaves a system where:

1. The human sensor operator has synthetic vision;
2. The pilot is a machine;
3. The operation and safety of the flight is held by a human (different from the sensor operator) who is designated the Pilot-in-Command;
4. No communications is allowed between the human sensor operator and the machine pilot or the human sensor operator and the human Pilot-in-Command lest the human sensor operator influence the machine pilot or the human Pilot-in-Command where or how to fly the aircraft. Otherwise, it might be considered as contributing to piloting the aircraft. This also results in a decidedly sub-optimal system.

Frankly, it is stupid to cripple the utility of a UAV system in order to avoid paying a small patent licensing fee. Besides, the '724 patent is for the use of synthetic vision in a Remotely Piloted Aircraft. It is not limited to the use of synthetic vision by the crew member designated as the Pilot.

An autonomous pilot would have to be really good.

Even after 100 years of aviation, pilots still encounter situations and problems that have not been seen before. The way they deal with new situations and problems is to use their experience, judgment, and even intuition. Pilots have been remarkably successful in saving passengers and crew under extremely difficult conditions such as when parts of their aircraft fall off (the top of the fuselage peels off) or multiply-redundant critical controls fail (no rudder control). Computers cannot be programmed to display judgment. They can only be programmed to display judgment-like behavior under conditions that have already been anticipated. UAVs should not be allowed to fly over people's houses until they are at least smart enough to turn on their own fuel supply.

[On Apr. 25, 2006 the Predator UAV being used by the U.S. Customs and Border Protection agency to patrol the border crashed in Nogales, Ariz. According to the NTSB report (NTSB Identification CHI06MA121) when the remote pilot switched from one console to another the Predator was inadvertently commanded to shut off its fuel supply and "With no engine power, the UAV continued to descend below line-of-site communications and further attempts to re-establish contact with the UAV were not successful." In other words, the Predator crashed because the system did not warn the remote pilot he had turned off the fuel supply and it was not smart enough to turn its fuel supply back on. [/Ref. 40!](#)]

An autonomous UAV assumes the computer program has no bugs.

Complex computer programs always have bugs no matter how brilliant or motivated the programmer(s). As an example, look at almost every computer program ever written.

An autonomous Unmanned Combat Aerial Vehicle (UCAV) will have little chance against one flown by an experienced pilot using Synthetic Vision until Artificial Intelligence produces a sentient, conscious

Being. At that point, all bets will be off because a superior sentient artificial Being may decide that war is stupid and refuse to participate. It may also decide that humans are obsolete or are fit only to be its slaves.

I propose yearly fly-offs:

1. A UCAV flown and fought autonomously against an F-22 (or F-35).
2. A UCAV flown and fought by a human pilot using synthetic vision against an F-22 (or F-35).
3. A UCAV flown and fought by a human pilot using synthetic vision against a UCAV flown and fought autonomously.

And that is the future of Unmanned Aerial Systems.

References

Reference 1 - *Synthetic Vision Technology for Unmanned Systems: Looking Back and Looking Forward* by Jeff Fox, Michael Abernathy, Mark Draper and Gloria Calhoun, AUVSI's **Unmanned Systems**, December 2008, pages 27-28.

This article has been reproduced with the permission of the Association for Unmanned Vehicle Systems International (AUVSI), which is the world's largest non-profit organization devoted exclusively to advancing the unmanned systems community. AUVSI, with members from government organizations, industry and academia, is committed to fostering, developing, and promoting unmanned systems and related technologies. <http://www.auvsi.org/>

PDF: http://www.jmargolin.com/svr/refs/ref01_auvsi.pdf

For the purposes of this response the article has been converted to text and the paragraphs have been numbered for easy reference: http://www.jmargolin.com/svr/refs/ref01_auvsi.htm

Reference 2 – U.S. Patent 5,593,114 **Synthetic Vision Automatic Landing System** issued January 14, 1997 to Ruhl (Assignee McDonnell Douglas Corporation).

Html copy at USPTO Patent Database:

<http://patft.uspto.gov/netacgi/nph-Parser?Sect1=PTO1&Sect2=HITOFF&d=PALL&p=1&u=%2Fmetahtml%2FPTO%2Fsrchnum.htm&r=1&f=G&l=50&s1=5,593,114.PN.&OS=PN/5,593,114&RS=PN/5,593,114>

PDF copy (complete with drawings): http://www.jmargolin.com/svr/refs/ref02_5593114.pdf

Reference 3 - **Synthetic Vision Technology Demonstration, Volume 1 of 4, Executive Summary**; Synthetic Vision Program Office Federal Aviation Administration; Malcolm A. Burgess, FAA; Terence Chang, TRW; Dale E. Dunford, USAF; Roger H. Hoh, Hoh Aeronautics; Walter F. Home, GTRI; Richard F. Tucker, TRW; December 1993. <http://www.dtic.mil/srch/doc?collection=t2&id=ADA280564>

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref03_old_faa_1993.pdf

Reference 4 – **Multi-Crew Pictorial Format Display Evaluation**; AFWAL-TR-87-3047; T.C. Way, R.L. Martin, J.G. Gilmour, M.E. Hornsby, R.E. Edwards; Final Report For Period May 1984 – January 1987, Boeing Military Airplane Company, February 1987. <http://handle.dtic.mil/100.2/ADA189349>

Mirrored copy: http://www.jmargolin.com/svr/refs/ref04_pictorial_format.pdf

Reference 5 – **FAA current definition of Synthetic Vision**

FAA Title 14 Part 1

The FAA definition of synthetic vision from: <http://ecfr.gpoaccess.gov/cgi/t/text/text-idx?c=ecfr&sid=41b1c51ea8ec4c9d1c5ebb94bbf28138&rqn=div8&view=text&node=14:1.0.1.1.1.0.1.1&idno=14>

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref05_faa.pdf

Title 14: Aeronautics and Space

PART 1—DEFINITIONS AND ABBREVIATIONS

Synthetic vision means a computer-generated image of the external scene topography from the perspective of the flight deck that is derived from aircraft attitude, high-precision navigation solution, and database of terrain, obstacles and relevant cultural features.

Synthetic vision system means an electronic means to display a synthetic vision image of the external scene topography to the flight crew.

Reference 6 – FAA Synthetic Vision is based on the use of a Digital Elevation Database

FAA SV Issues- Part 23 Position

http://www.faa.gov/aircraft/air_cert/design_approvals/transport/media/Pt23ApproachSlides.pdf

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref06_Pt23ApproachSlides.pdf

Federal Aviation Administration Part 23 Synthetic Vision Approval Approach

Presentation to: FAA Synthetic Vision Workshop

Name: Lowell Foster

Date: Feb 14, 2006

Page 13:

SV Issues - Part 23 Position

Terrain Data Confidence Issues Cont.

- Complete database accuracy impossible to validate
- **Everyone gets their data from the same original source**
- Manufacturers are doing everything possible to verify the current data is accurate, but that is really just a confidence builder

If accuracy of data base must be validated then SV is unapproveable.

Page 14:

PositionRisk Management / Mitigation of Terrain Uncertainties

- No operational credit for SV –current minimums still apply
- Significant safety benefits possible –outweighs what we consider minimal risk
- Experience -large data base errors to date have been easy to recognize and report –very visible on PFD and map display
- Small data base errors such as an elevation point are likely to be insulated, so exposure to a misleading information situation is considered small
- Current resolution tends to round-up the elevation data** so that small errors are not as significant and on the conservative side

Reference 7 – Digital Elevation Model: <http://data.geocomm.com/dem/>

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref07_usgs_dem.pdf

The USGS Digital Elevation Model (DEM) data files are digital representations of cartographic information in a raster form. DEMs consist of a sampled array of elevations for a number of ground positions at regularly spaced intervals. These digital cartographic/geographic data files are produced by the U.S. Geological Survey (USGS) as part of the National Mapping Program and are sold in 7.5-minute, 15-minute, 2-arc-second (also known as 30-minute), and 1-degree units. The 7.5- and 15-minute DEMs are included in the large scale category while 2-arc-second DEMs fall within the intermediate scale category and 1-degree DEMs fall within the small scale category - (Source: USGS)

Reference 8 – Digital Elevation Database improved by a Space Shuttle mission.

<http://spaceflight.nasa.gov/shuttle/archives/sts-99/>

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref08_sts99.pdf

STS-99 Crew Works in Shifts to Complete Mapping Mission

Endeavour's international crew of seven spent 11 days in orbit during February 2000 mapping the Earth's surface with radar instruments.

-
-
-

Space Shuttle Endeavour Maps the World in Three Dimensions

The main objective of STS-99 was to obtain the most complete high-resolution digital topographic database of the Earth.

The Shuttle Radar Topography Mission, or SRTM, was an international project spearheaded by the National Imagery and Mapping Agency and NASA, with participation of the German Aerospace Center, DLR. SRTM consisted of a specially modified radar system that flew onboard

the space shuttle during STS-99. This radar system gathered data that produced unrivaled 3-D images of the Earth's surface.

Reference 9 – Honeywell IFPD Synthetic Vision System

http://www.honeywell.com/sites/portal?page=ipfd_primus&smap=aerospace&theme=T5

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref09_honeywell.pdf

**Reference 10** - NASA description of the HiMAT project:

<http://www.nasa.gov/centers/dryden/news/FactSheets/FS-025-DFRC.html>

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref10_nasa_himat.pdf

Reference 11 - Simulator Evaluation of a Remotely Piloted Vehicle Lateral Landing Task Using a Visual Display, Shahan K. Sarrafian

NASA Technical Memorandum 84916 (May 1984):

http://www.nasa.gov/centers/dryden/pdf/87968main_H-1205.pdf

http://www.jmargolin.com/svr/refs/ref11a_sarrafian.pdf

NASA Technical Memorandum 85903 (August 1984):

http://www.nasa.gov/centers/dryden/pdf/87986main_H-1246.pdf

http://www.jmargolin.com/svr/refs/ref11b_sarrafian.pdf

I converted this article to text in order to make it easier to search and to quote from.

http://www.jmargolin.com/svr/refs/ref11c_sarrafian.doc . The downloaded PDF file is the controlling version.

Reference 12 - NASA Aviation NavigationTutorial: <http://virtualskies.arc.nasa.gov/navigation/tutorial/tutorial3.html>Mirrored copy: http://www.jmargolin.com/svr/refs/ref12_nasa_ils.pdf**Reference 13 – THE ROLE OF SIMULATION IN THE DEVELOPMENT AND FLIGHT TEST OF THE HIMAT VEHICLE**, M. B. Evans and L. J. Schilling, NASA-TM-84912, April 1984http://www.nasa.gov/centers/dryden/pdf/87962main_H-1190.pdfMirrored Copy: http://www.jmargolin.com/svr/refs/ref13_evans_schilling.pdf

From PDF page 13:

Visual Landing Aid

Actual. - Cues to the pilot during landing included the cockpit instruments, ILS/glideslope error indicators, television transmission from the vehicle, calls on the radio from the chase pilot, and space-positioning calls from the flight-test engineer.

Simulation model. - For most of the program, the landing cues for the pilot in a HiMAT simulation included only the instruments, mapboards, and the ILS/glideslope error indicators. Although these are all valid cues, they could not achieve the same effect as the television transmission used in actual flight. During flight, as soon as the pilot can identify the runway, his scan focuses more on the television picture and less on the cockpit instruments. To help alleviate this lack of fidelity in the simulation, a display of the runways on the dry lakebed was developed on a recently purchased Evans and Sutherland Graphics System.

Reference 14 - Visual-Proprioceptive Cue Conflicts in the Control of Remotely Piloted Vehicles, Reed, 1977, AFHRL-TR-77-57<http://www.dtic.mil/srch/doc?collection=t2&id=ADA049706><http://handle.dtic.mil/100.2/ADA049706>Mirrored Copy: http://www.jmargolin.com/svr/refs/ref14_reed.pdf

Page 5 (PDF page 8):

VISUAL PROPRIOCEPTIVE CUE CONFLICTS IN THE CONTROL OF REMOTELY PILOTED VEHICLES
I. INTRODUCTION

An investigation was made of operator tracking performance under conditions of visual proprioceptive conflict. (The term *proprioception* as used here refers to sensations arising from the receptors of the nonauditory labyrinth of the inner ear and from muscles, tendons, and joints. Kinesthesia refers to sensations of movement arising from the receptors other than the nonauditory labyrinth.) The experimental scenario is described as follows: An operator is asked to maneuver a remotely piloted vehicle (RPV) from an airborne control station (a mother ship). This station is equipped with a television monitor, control stick, and other controls and displays necessary to maneuver the RPV through a specified

course. The RPV, containing a television camera mounted in its nose, relays an image of the terrain to be displayed on the television monitor in the control station. Thus, the visual scene displayed to the operator represents the scene viewed by the camera. The task of the operator is to use the controls and displays to "fly" the RPV in much the same way he would fly a conventional aircraft.

The scenario is complicated by several factors. First, the visual inputs to the operator from the RPV are independent of the motion inputs from the control station. Thus, the operator will experience motion cues that are uncorrelated with the visual inputs received from the RPV. Second, while traditional pilot training programs operate on the philosophy that proprioceptive cues provided by the motion of the aircraft should be disregarded, research has shown that these cues are compelling, not easily ignored, and may improve performance when used in training simulators (see, for example, Borlace, 1967; Cohen, 1970; Douvillier, Turner, McLean, & Heinle, 1960; Fedderson, 1961; Huddleston & Rolfe, 1971; Rathert, Creer, & Douvillier, 1959; Ruocco, Vitale, & Benfari, 1965). The task simulated in the experiment presented here, however, required that the RPV operator disregard sensations of motion in order to maintain adequate performance. Under conditions of visual -proprioceptive conflict (as when the mother ship and/or the RPV are in turbulence) the stereotypic responses of pilots to correct angular accelerations will be inappropriate.

The objectives of the experiment were to obtain data applicable to the following.

1. The relative difficulty of controlling an RPV from an airborne station under different visual-motion combinations (e.g., visual-motion combinations that produce conflict, or no conflict).
2. The relative ability of pilots, navigators, and nonrated Air Force officers to operate an RPV from an airborne station (i.e., the effect of previous experience).
3. The differential effects of experience on the acquisition of skills necessary to operate an RPV.
4. Selection and training of potential RPV operators.
5. The need for motion in RPV training simulators.

II. METHOD

Simulation System

This research utilized the Simulation and Training Advanced Research System (STARS) facility of the Advanced Systems Division, Air Force Human Resources Laboratory, Wright Patterson Air Force Base, Ohio. The equipment consisted of an operator station mounted on a motion platform, hydraulic pump, terrain model, television camera and optical probe, experimenter station, and a Sigma 5 digital computer. A brief description of the hardware system is presented as follows.

Operator station. The operator station, illustrated in Figure 1, was designed to simulate the environment of an airborne control station. This station contained a television monitor that provided visual images relayed to h from a simulated RPV. These visual images were generated from a television camera and optical probe, which viewed the terrain model. The path followed by the camera and probe over the terrain model was commensurate with the vehicle flight path as determined by control stick

inputs provided by the subject. Since the control stick and visual system were independent of the motion platform, the capability existed for the subject to

5

[Figure 1. Operator station mounted on motion platform. *{not usable}*]

maneuver the simulated RPV under various environmental conditions. This arrangement permitted the introduction of conditions in which the RPV alone, the airborne station alone, or both, were under air turbulence.

The subject sat in an aircraft-type seat directly facing a 14- by 11-inch (35.6 by 27.9 cm) television monitor, which was mounted in a center sectional panel of the operator console. The distance between the subject's eyes and the center of the television screen was 28 inches (71.1 cm). The viewing angle subtended 28.07° in the lateral plane and 22.23° in the vertical plane of the monitor. An altimeter, altitude warning light, and an attitude director indicator (ADI) were mounted on a flat sectional panel to the left of the subject and at an angle of 45° from the center panel (See Figure 2). The altimeter was a vertical straight-scaled indicator with a moving pointer that provided altitude readings in feet above sea level. An amber altitude warning light flashed whenever the simulated RPV altitude dropped to a level, below 180 feet (54.9 m), remained on whenever altitude exceed 1,000 feet (304.8 m) and was off between 180 and 1,000 feet.

A 6-inch (15.2 cm) side-arm rate control stick was mounted on the right-hand side console armrest (see Figure 2). The control was a spring-centered stick with a dual-axis (fee positioning) capability that required 4 ounces, (113.4 g) breakout force. The same amount of force was needed to hold the stick at full deflection. The range of deflection on both lateral (right - left) and longitudinal (fore - aft) stick was 0 to 25° (henceforth referred to as 0 to 100 percent deflection).

In addition, the operator station contained a foot switch to allow the subject to communicate with the experimenters. White noise was input to the subject's headset to mask external disturbances. The aircraft seat was equipped with a standard harness and lapbelt to protect the subject. An air conditioner maintained the station at 70° F (21.1° C). Finally, incident illumination was at an average of .37 footcandles at eye level.

6

[Figure 2. Operator station instruments and control stick. *{not usable}*]

Motion system. The operator station was mounted on a motion platform that provided onset cues in two degrees of freedom of angular acceleration. Roll onset cues were provided by tilting the simulator about the longitudinal axis (i.e., the X axis) and pitch onset cues were provided by tilting the simulator about the lateral axis (i.e., the 'Y' axis). Motion was achieved by actuation of hydraulic cylinders mounted under the 9- by 8-feet (2.74 by 2.4 m) simulator platform, as shown in Figure 1.

Visual system. The visual system consisted of a three-dimensional terrain model (a modified SMK-23 Visual Simulator, The Singer Company), television camera and optical probe, and three monochromatic television monitors. The terrain model provided "real-world ground cues for visual tracking over the surface. The real-world to terrain model scale was 3,000:1 and represented a six by twelve-mile (9.65 by 19.3 km) area. The model was mounted on an endless belt that was servo-driven to represent the continuous changes in scene as the simulated RPV traveled along north-south directions. A television camera viewed the terrain model through an optical probe that contained a servoed mechanical

assembly to permit the introductions of heading, roll, and pitch. Both the camera and probe were mounted on a servo-driven carriage system that moved across the terrain model to simulate movement of the RPV along east-west directions and in and out to simulate altitude changes. The field of view represented on the television monitor subtended a viewing angle of 50° horizontally and 38° vertically over the terrain model. One television monitor was mounted in the operator station and the other two were located in the experimenter station. All three monitors had a 1,000-line resolution vertically.

Experimenter station. The experimenter station contained the equipment necessary to monitor the status of the hardware/software and control activities of the subject, and to setup the various stimulus conditions. This station was manned by two experimenters. The task of the first was to prepare the system for operation, insure that all hardware was operating effectively and reliably prior and during the experiment, and set up the conditions for all experimental trials in accordance with a prepared check list. The task of the second experimenter was to determine the appropriate time for introducing specific stimuli to the subject. When certain criteria were met, the experimenter pressed a discrete hand-held insert button to initiate a stimulus trial.

Computer system and interfaces. A Sigma 5 digital computer was used to drive the peripheral equipment, and to record data during experimental runs. Resident software consisted of a real-time aerodynamic mathematical model, executive routine, and data recording programs. The

7

Reference 15 - Lunar Driving Simulator History

<http://www.knology.net/~skeetv/SimHist3.html>

Mirrored copy: http://www.jmargolin.com/svr/refs/ref15_lunar_driving_history.pdf

Reference 16 - Evans & Sutherland Picture System:

Short Brochure: <http://www.computerhistory.org/brochures/companies.php?alpha=d-f&company=com-42b9d8b7f4191>

Full Brochure:

http://archive.computerhistory.org/resources/text/Evans_Sutherland/EvansSutherland.3D.1974.102646288.pdf

Mirrored copy:

Short Brochure: http://www.jmargolin.com/svr/refs/ref16_esps_s.pdf

Full Brochure: http://www.jmargolin.com/svr/refs/ref16_esps_f.pdf

Reference 17 – RC AeroChopper Review: <http://www.atarimagazines.com/startv3n9/rcaerochopper.html>

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref17_aerochopper.pdf

Reference 18 – Microsoft Flight Simulator

Microsoft Flight Simulator 5.1 Screen Shot:

http://www.jmargolin.com/svr/refs/ref18_fs5_1_screenshot.pdf

Microsoft Flight Simulator History: http://www.jmargolin.com/svr/refs/ref18_fs_history.pdf

Reference 19 – Microsoft Flight Simulator's first use of terrain points:

[http://www.flightsim.com/cgi/kds?\\$\\$=main/review/fs2000.htm](http://www.flightsim.com/cgi/kds?$$=main/review/fs2000.htm)

Mirrored copy: http://www.jmargolin.com/svr/refs/ref19_fs_first.pdf

Reference 20 – News releases from RTI (Research Triangle Institute), Avidyne, AvroTec, and NASA announcing NASA had selected those companies to develop a synthetic vision system for General Aviation. www.jmargolin.com/svr/refs/ref20_nasa1999.pdf

Reference 21: NASA press release, May 13, 1999, <http://quest.nasa.gov/aero/news/05-13-99.txt>

Mirrored copy: http://www.jmargolin.com/svr/refs/ref21_nasa_pr.pdf

Michael Braukus
Headquarters, Washington, DC
(Phone: 202/358-1979)

May 13, 1999

Kathy Barnstorff
Langley Research Center, Hampton, VA
(Phone: 757/864-9886)

RELEASE: 99-59

SYNTHETIC VISION COULD HELP PILOTS STEER CLEAR OF FATALITIES

NASA and industry are developing revolutionary cockpit displays to give airplane crews clear views of their surroundings in bad weather and darkness, which could help prevent deadly aviation accidents.

Limited visibility is the greatest factor in most fatal aircraft accidents, said Michael Lewis, director of the Aviation Safety Program at NASA's Langley Research Center in Hampton, VA. NASA has selected six industry teams to create Synthetic Vision, a virtual-reality display system for cockpits, offering pilots an

electronic picture of what's outside their windows, no matter the weather or time of day.

"With Global Positioning Satellite signals, pilots now can know exactly where they are," said Lewis. "Add super-accurate terrain databases and graphical displays and we can draw three-dimensional moving scenes that will show pilots exactly what's outside. The type of accidents that happen in poor visibility just don't happen when pilots can see the terrain hazards ahead."

The NASA Aviation Safety Program envisions a system that would use new and existing technologies to incorporate data into displays in aircraft cockpits. The displays would show hazardous terrain, air traffic, landing and approach patterns, runway surfaces and other obstacles that could affect an aircraft's flight.

Industry teams submitted 27 proposals in four categories: commercial transports and business jets, general aviation aircraft, database development and enabling technologies. NASA and researchers from the Federal Aviation Administration and Department of Defense evaluated the proposals' technical merit, cost and feasibility.

NASA has committed \$5.2 million that will be matched by \$5.5 million in industry funds to advance Synthetic Vision projects over the next 18 months. More money is expected to be designated later to accelerate commercialization and make some systems available within four to six years.

Among the team leaders selected for the first phase of the program are: Rockwell Collins, Inc., Cedar Rapids, IA; AvroTec, Inc., Portland, OR; Research Triangle Institute, Research Triangle Park, NC; Jeppesen-Sanderson, Inc., Englewood, CO; the Avionics Engineering Center of Ohio University, Athens, OH; and Rannoch Corporation, Alexandria, VA.

Rockwell Collins, Inc. will receive funds to develop synthetic vision for airliners and business jets. The AvroTec, Inc. and Research Triangle Institute groups will use their awards to create technologies for a general-aviation synthetic vision system. A team led by Jeppesen-Sanderson, Inc. will receive funds to develop terrain database requirements and system approaches. The Avionics Engineering Center of Ohio University and Rannoch Corporation will use their awards to design specific component technologies for Synthetic Vision.

The Aviation Safety Program is a partnership with the FAA, aircraft manufacturers, airlines and the Department of Defense.

This partnership supports the national goal announced by President Clinton to reduce the fatal aircraft accident rate by 80 percent in 10 years and by 90 percent over 25 years.

Because of advances in the last 40 years, commercial airliners are already the safest of all major forms of transportation. But with an accident rate that has remained relatively constant in the last decade and air traffic expected to triple over the next 20 years, the U.S. government wants to prevent a projected rise in the number of aircraft accidents.

For a complete list of industry teams please check the Internet at:

http://oea.larc.nasa.gov/news_rels/1999/May99/99-025.html

- end -

Reference 22 – Virtual Cockpit Window" for a Windowless Aerospacecraft, NASA Tech Briefs. January 2003, page 40. <http://www.nasatech.com/Briefs/Jan03/MSC23096.html>
Mirrored Copy: http://www.jmargolin.com/svr/refs/ref22_nasa_techbriefs.pdf

"Virtual Cockpit Window" for a Windowless Aerospacecraft

Wednesday, January 01 2003

A software system processes navigational and sensory information in real time to generate a three- dimensional- appearing image of the external environment for viewing by crewmembers of a windowless aerospacecraft. The design of the particular aerospacecraft (the X-38) is such that the addition of a real transparent cockpit window to the airframe would have resulted in unacceptably large increases in weight and cost.

When exerting manual control, an aircrew needs to see terrain, obstructions, and other features around the aircraft in order to land safely. The X-38 is capable of automated landing, but even when this capability is utilized, the crew still needs to view the external environment: From the very beginning of the United States space program, crews have expressed profound dislike for windowless vehicles. The well-being of an aircrew is considerably promoted by a three-dimensional view of terrain and obstructions. The present software system was developed to satisfy the need for such a view. In conjunction with a computer and display equipment that weigh less than would a real transparent window, this software system thus provides a "virtual cockpit window."

The key problem in the development of this software system was to create a realistic three-dimensional perspective view that is updated in real time. The problem was solved by building upon a pre-existing commercial program — LandForm C3 — that combines the speed of flight-simulator software with the power of geographic-information-system software to generate real-time, three-dimensional-appearing displays of terrain and other features of flight environments. In the development of the present software, the pre-existing program was modified to enable it to utilize real-time information on the position and attitude of the aerospacecraft to generate a view

of the external world as it would appear to a person looking out through a window in the aerospacecraft. The development included innovations in realistic horizon-limit modeling, three-dimensional stereographic display, and interfaces for utilization of data from inertial-navigation devices, Global Positioning System receivers, and laser rangefinders. Map and satellite imagery from the National Imagery and Mapping Agency can also be incorporated into displays.

After further development, the present software system and the associated display equipment would be capable of providing a data-enriched view: In addition to terrain and obstacles as they would be seen through a cockpit window, the view could include flight paths, landing zones, aircraft in the vicinity, and unobstructed views of portions of the terrain that might otherwise be hidden from view. Hence, the system could also contribute to safety of flight and landing at night or under conditions of poor visibility.

In recent tests, so precise was the software modeling that during the initial phases of the flight the software running on a monitor beside the video camera produced nearly identical views.

This work was done by Michael F. Abernathy of Rapid Imaging Software, Inc., for Johnson Space Center. For further information, please contact Michael F. Abernathy, Rapid Imaging Software, Inc., 1318 Ridgcrest Place S.E., Albuquerque, NM 87108. MSC-23096.

Reference 23 – Press Release from Rapid Imaging Software, Inc. (<http://www.landform.com/pages/PressReleases.htm>) which states (near the bottom of the page): Mirrored copy: http://www.jmargolin.com/svr/refs/ref23_ris.pdf



On December 13th, 2001, Astronaut Ken Ham successfully flew the X-38 from a remote cockpit using LandForm VisualFlight as his primary situation awareness display in a flight test at Edwards Air Force Base, California. This simulates conditions of a real flight for the windowless spacecraft, which will eventually become NASA's Crew Return Vehicle for the ISS. We believe that this is the first test of a hybrid synthetic vision system which combines nose camera video with a LandForm synthetic vision display. Described by astronauts as "the best seat in the house", the system will ultimately make space travel safer by providing situation awareness during the landing phase of flight.

Reference 24 – **Description of Path-in-the-Sky Contact Analog Piloting Display**, Charles E. Knox and John Leavitt, October 1977, NASA Technical Memorandum 74057 http://ntrs.nasa.gov/archive/nasa/casi.ntrs.nasa.gov/19780002119_1978002119.pdf

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref24_knox.pdf

Reference 25 - "The Electronic Terrain Map: A New Avionics Integrator", Small, D.M. USAF, Avionics Laboratory, Wright-Patterson AFB, OH, AIAA-1981-2289. In: Digital Avionics Systems Conference, 4th, St. Louis, MO, November 17-19, 1981, Collection of Technical Papers. (A82-13451 03-04) New York, American Institute of Aeronautics and Astronautics, 1981, p. 356-359.

http://www.jmargolin.com/svr/refs/ref25_small.pdf

Converted to text using OCR: http://www.jmargolin.com/svr/refs/ref25_small.html

Reference 26 - This is part of the Washington Sectional Aeronautical Chart, Scale 1:500,000 55th Edition, published March 3, 1994 by U.S. Department of Commerce National Oceanic and Atmospheric Administration National Ocean Service.

Map: http://www.jmargolin.com/svr/refs/ref26_pmap1.pdf

Washington Legend showing paper map symbology: http://www.jmargolin.com/svr/refs/ref26_pmap2.pdf

Reference 27 - Using Synthetic Images to Register Real Images with Surface Models; Horn, Berthold K.P.; Bachman, Brett L. ; August 1977.

MIT DSpace: <http://hdl.handle.net/1721.1/5761>

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref27_horn.pdf

Abstract: A number of image analysis tasks can benefit from registration of the image with a model of the surface being imaged. Automatic navigation using visible light or radar images requires exact alignment of such images with digital terrain models. In addition, automatic classification of terrain, using satellite imagery, requires such alignment to deal correctly with the effects of varying sun angle and surface slope. Even inspection techniques for certain industrial parts may be improved by this means.

Reference 28 - U.S. Patent 3,328,795 **Fixtaking Means and Method** issued June 27, 1967 to Hallmark.

USPTO Database (Does not have http version): <http://patft.uspto.gov/netacgi/nph-Parser?Sect1=PTO1&Sect2=HITOFF&d=PALL&p=1&u=%2Fnetacgi%2FPTO%2Fsrchnum.htm&r=1&f=G&l=50&s1=3,328,795.PN.&OS=PN/3,328,795&RS=PN/3,328,795>

PDF Version: http://www.jmargolin.com/svr/refs/ref28_3328795.pdf

Reference 29 – U.S. Patent 4,347,511 **Precision navigation apparatus** issued August 31, 1982 to **Hofmann, et al.**

From USPTO: <http://patft.uspto.gov/netacgi/nph-Parser?Sect1=PTO1&Sect2=HITOFF&d=PALL&p=1&u=%2Fnetacgi%2FPTO%2Fsrchnum.htm&r=1&f=G&l=50&s1=4,347,511.PN.&OS=PN/4,347,511&RS=PN/4,347,511>

PDF Version: http://www.jmargolin.com/svr/refs/ref29_4347511.pdf

Converted to text using OCR (with the paragraphs numbered):

http://www.jmargolin.com/svr/refs/ref34_vcass.htm

Reference 35 – The earliest known description of the invention that became U.S. Patent 5,566,073 **Pilot Aid Using A Synthetic Environment**. http://www.jmargolin.com/svr/refs/ref35_pilotdoc.pdf

Reference 36 - U.S. Patent 5,566,073 **Pilot Aid Using A Synthetic Environment** issued October 15, 1996 to Margolin

USPTO (html): <http://patft.uspto.gov/netacgi/nph-Parser?Sect1=PTO1&Sect2=HITOFF&d=PALL&p=1&u=%2Fnethtml%2FPTO%2Fsrchnum.htm&r=1&f=G&l=50&s1=5,566,073.PN.&OS=PN/5,566,073&RS=PN/5,566,073>

PDF: http://www.jmargolin.com/svr/refs/ref36_5566073.pdf

Reference 37 – U.S. Patent 5,904,724 **Method and apparatus for remotely piloting an aircraft** issued May 18, 1999 to Margolin

USPTO (html): <http://patft.uspto.gov/netacgi/nph-Parser?Sect1=PTO1&Sect2=HITOFF&d=PALL&p=1&u=%2Fnethtml%2FPTO%2Fsrchnum.htm&r=1&f=G&l=50&s1=5,904,724.PN.&OS=PN/5,904,724&RS=PN/5,904,724>

PDF: http://www.jmargolin.com/svr/refs/ref37_5904724.pdf

Reference 38 - U.S. Patent Application Publication 20080033604 **System and Method For Safely Flying Unmanned Aerial Vehicles in Civilian Airspace**

USPTO (html): <http://appft1.uspto.gov/netacgi/nph-Parser?Sect1=PTO2&Sect2=HITOFF&u=%2Fnethtml%2FPTO%2Fsearch-adv.html&r=18&p=1&f=G&l=50&d=PG01&S1=%22synthetic+vision%22&OS=%22synthetic+vision%22&RS=%22synthetic+vision%22>

PDF: http://www.jmargolin.com/svr/refs/ref38_pg3604.pdf

Reference 39 – Letter sent to Optima Technology Group by Rapid Imaging Software attorney Benjamin Allison, dated October 13, 2006. http://www.jmargolin.com/svr/refs/ref39_ris.pdf

Reference 40 - NTSB Incident Report on crash of Predator on April 25, 2006, northwest of Nogales, NM. NTSB Identification **CHI06MA121**

http://www.nts.gov/ntsb/brief.asp?ev_id=20060509X00531&key=%201

Mirrored Copy: http://www.jmargolin.com/svr/refs/ref40_ntsb.pdf

.end

Exhibit

15

Jed Margolin

From: "Brett Davis" <davis@auvsi.org>
To: "Jed Margolin" <auvsi@jmargolin.com>
Sent: Friday, January 30, 2009 4:25 PM
Subject: RE: Hi from Brett at AUVSI

Mr. Margolin,

Thank you for your response to the article that we discussed.

While I'm not disputing your technical points, for me the point of the story was, as it said early on, to "focus on select systems that were important enablers toward UAS synthetic vision systems." If the terminology is rather loosely applied in the story that's probably my fault as much as anyone's, but I feel it's sufficient for the purposes of an overview story in the magazine. I also don't think that having the story published should interfere with your legal claims as it's not in any way a legal document.

My inclination is not to run anything else in the magazine. Editors generally feel that it's confusing to refer readers off-site to responses to articles that ran some months ago.

That said, I would recommend that you post your links and whatever statements you'd like to make in our Forum section, which is open to all, not just members. It's reachable via a link on the homepage. That will give you a little more "room to roam" in terms of posting your explanation. In the future we hope to have a web-based magazine display that will allow comments, but we're not there yet.

Thanks again,
 Brett

Brett Davis
 Editor
 AUVSI
 2700 South Quincy Street Suite 400
 Arlington, VA 22206
 davis@auvsi.org

 Don't Miss...

AUVSI's Unmanned Systems Program Review 2009

February 3-5, 2009

Mandarin Oriental - Washington, DC, USA

For more information visit: <http://www.auvsi.org/programreview/>

From: Jed Margolin [mailto:auvsi@jmargolin.com]
Sent: 2009-01-19 19:19
To: Brett Davis
Subject: Fw: Hi from Brett at AUVSI

Mr. Davis.

Did you receive the email I sent you on 1/8/2009?

Assuming you did, what did you think about my response?

Jed Margolin

=====

A127

----- Original Message -----

From: [Jed Margolin](#)
To: [Brett Davis](#)
Sent: Thursday, January 08, 2009 11:34 AM
Subject: Re: Hi from Brett at AUVSI

Dear Mr. Davis.

Thank you for permission to post the article **Synthetic Vision Technology for Unmanned Systems: Looking Back and Looking Forward** by Jeff Fox, Michael Abernathy, Mark Draper and Gloria Calhoun which appeared in the December 2008 issue of AUVSI's Unmanned Systems magazine.

I expect that the response I have written is too long to print in the magazine (It's 57 pages.) The abridged version is also probably too long. (20 pages). I have attached both versions so you can judge for yourself.

I have done html versions with active links to the references and placed them in a protected directory at:

http://www.jmargolin.com/svr/auvsi_response_index.htm

Username: **Serenity**
Password: **Firefly**

{Case sensitive}

I expect to unprotect the directory soon to make it publicly available.

Would it be possible for you to print something like the following in the magazine?

AUVSI member Jed Margolin has taken strong exception to the article **Synthetic Vision Technology for Unmanned Systems: Looking Back and Looking Forward** by Jeff Fox, Michael Abernathy, Mark Draper and Gloria Calhoun which appeared in the December 2008 issue of AUVSI's Unmanned Systems magazine.

Unfortunately, his response is too long to print here.

In the interests of fairness we are providing the URL to where he has posted his response on his personal web site:
http://www.jmargolin.com/svr/auvsi_response_index.htm

The posting of this URL does not imply AUVSI's endorsement of Margolin's opinions. Mr. Margolin's opinions are his own.

It should be noted that his opinions about the history and the future of synthetic vision are markedly different from those of authors Fox, Abernathy, Draper and Calhoun.

Sincerely yours,

Jed Margolin

=====

----- Original Message -----

From: [Brett Davis](#)
To: auvsi@jmargolin.com
Sent: Tuesday, January 06, 2009 6:42 AM
Subject: Hi from Brett at AUVSI

Mr. Margolin,

We spoke a bit in December about the synthetic vision article. I said I would get you a PDF copy but I still haven't gotten

A128

the final PDF from the printer, although I expect to get that today. Once I have it I can pull that article out and send it along.

It isn't possible for us to post it openly on our website (yet, anyway; that's being redesigned). You have permission to post it on yours if you will include a link back to our site.

Thanks! Stay tuned, I'll send that along when I get it.

Brett

Brett Davis
Editor
AUVSI
703-845-9671 x 208
571-480-1007 (mobile)
davis@auvsi.org